


Palm Beach Gardens

Elementary School

GUARANTEED MAXIMUM PRICE REPORT

March 28, 2007



C.R.Klewin

CONSTRUCTION
MANAGERS

Palm Beach Gardens Elementary School

Table of Contents

Guaranteed Maximum Price Report – March 28, 2007

- ✚ Letter
- ✚ Assumptions and Clarifications
- ✚ Allowances
- ✚ Estimate
- ✚ Schedule
- ✚ Documents



C.R. Klewin
CONSTRUCTION
MANAGERS



C.R. KLEWIN SOUTHEAST, INC.
NORTHPOINT CORPORATE CENTER
701 NORTHPOINT PKWY., STE 318
WEST PALM BEACH, FL 33407
(561) 683-5400
FAX: (561) 683-5076
CGC 038422

March 28, 2007

Mr. Glen Armbruster
School District of Palm Beach County
3320 Forest Hill Blvd.
West Palm Beach, FL 33406

**RE: Palm Beach Gardens Elementary School
SDPBC Project No. 0111-7505
100% Construction Documents GMP Submittal**

Dear Mr. Armbruster:

We are pleased to submit the enclosed Guaranteed Maximum Price Report for the Palm Beach Gardens Elementary School Project. The Report is based on "100% Construction Documents Resubmittal Dated October 25, 2006" prepared by PGAL Architects.

We also include the requirements of ASI #1 dated 3-20-07 as further defined in the Assumptions and Clarifications section of this report.

We calculate the enclosed floor area (Including Covered Walkways at 50%) to be 119,000 s.f.

We acknowledge the requirements of the "Master Controlled Insurance Program" and the "Commissioning Statement". Please refer to the Assumptions and Clarifications section of this Report for our comments regarding these requirements.

The GMP Construction Cost Estimate is \$23,430,747.

The 100 % CD Phase III Construction Cost Estimate was \$23,325,000.

Our Estimate is priced based on a construction start of June, 2007.

Exhibits "B" and "S" are attached to this letter.

We would be pleased to discuss these issues at our next committee meeting or at your convenience. Should you have any questions or comments, please do not hesitate to call me at (561)-683-5400.

Sincerely,

C. R. Klewin Southeast, Inc.



Greg Bischof
Sr. Vice President

EXHIBIT B

PALM BEACH GARDENS ELEMENTARY SCHOOL
PROJECT NO. 0111-7505

DIVISION

1	GENERAL REQUIREMENTS (DIRECT COST ITEMS RELATED TO SITE)	\$ 433,710
2	SITE CONSTRUCTION	\$ 3,424,748
3	CONCRETE	\$ 2,853,156
4	MASONRY	\$ 150,516
5	STEEL	\$ 1,422,250
6	CARPENTRY	\$ 635,600
7	THERMAL/MOISTURE PROTECTION	\$ 808,317
8	WINDOWS AND DOORS	\$ 982,300
9	FINISHES	\$ 2,450,187
10	SPECIALTIES	\$ 531,175
11	EQUIPMENT	\$ 451,650
12	FURNISHINGS	\$ 30,836
13	SPECIAL CONSTRUCTION	\$ 99,000
14	ELEVATOR	\$ 46,500
15	MECHANICAL	\$ 3,365,100
16	ELECTRICAL	\$ 2,723,700

TOTAL Divisions 1 through 16 \$ 20,408,745

P. & P. BONDS and GENERAL LIABILITY INSURANCE	\$ 436,260
CONSTRUCTION PHASE FEE (ON SITE STAFF)	\$ 995,850
GENERAL CONDITIONS (DIRECT COST ITEMS RELATED TO FIELD STAFF)	\$ 69,750
CONSTRUCTION MANAGER FEE	\$ 980,329
CONSTRUCTION CONTINGENCY	\$ 600,000

DEDUCT SALES TAX RECOVERY (GUARANTEED)	\$ (219,725)
TOTAL GUARANTEED MAXIMUM PRICE	\$ 23,271,208
PRE-CONSTRUCTION PHASE FEE	\$ 159,539

TOTAL CONSTRUCTION COST (PRE-CONSTRUCTION FEE + GMP) \$ 23,430,747

Certified True and Correct by:

Project Executive 
Name and Title: Greg Bischof, Sr, Vice President

Dated
3/28/2007

**EXHIBIT S
 SUBCONTRACTOR'S PARTICIPATION
 DIVISION 1 - 16**

PROJECT NAME: PALM BEACH GARDENS ELEMENTARY SCHOOL

PROJECT NO: PBC SD: 0111-7505

APPROVED GMP AMOUNT: \$23,430,000

Subject to agreement with the Construction manager, the Subcontractor firms listed below will participate in this project as shown below.

ITEM #	DESCRIPTION	COST	BUDGET	NAME	M/WBE	AMOUNT	%
1.1	Survey			Velcon Group, Inc.	yes	\$27,200	0.1%
2.1	Demolition			Omega Contracting, Inc.	yes	\$266,825	1.1%
7.1	Roofing			A-1 Duran Roofing, Inc.	yes	\$629,350	2.7%
9.3	Flooring			Zaharion's Flooring	yes	\$331,050	1.4%
9.4	Painting			Fleischer's Painting	yes	\$182,895	0.8%
15.1	H V A C			Hyvac	yes	\$2,252,150	9.6%

Subcontractors represented as M/WBE Certified are according to requirements established in the Proposal Documents. Attach a copy of the Certification for each Subcontractor listed.

CONTRACTOR'S FIRM NAME: C. R. KLEWIN SOUTHEAST, INC. Total M/WBE Participation: \$3,689,470

Name and Position: Greg Bischof, Sr. Vice President

Total Percentage 15.7%

SIGNATURE: 

Date: March 28, 2007

ASSUMPTIONS AND CLARIFICATIONS

Palm Beach Gardens Elementary School

1. We assume that the Notice to Proceed will be issued on or about June 1, 2007.
2. We assume the Project Site will not be occupied during construction/that students will not be present during any of the construction activities and that background screening as required by State of Florida – The Jessica Lunsford Act will not apply.
3. We assume all costs incurred for Permit fees, Impact fees, Governmental, fees Utility Connection fees, and Utility Meter costs will be paid for by the Owner.
4. We assume all cost incurred for material testing, system testing, special inspections, threshold inspections, and/or special testing will be paid for by the Owner.
5. Builders Risk Insurance is not included. ~~We assume the owner will provide Builder's Risk and any deductible cost for Named Storm occurrence will be funded from the project contingency and/or by the Owner.~~
6. ~~We assume the intent of the owner direct purchase program provides direct payment to suppliers and or manufacturers of construction products that become a permanent part of the project. Should any Trade Contractor selected for the project, refuse to provide their suppliers and or manufactures information so Owner Purchase Orders and Owner payments can be transmitted directly to the actual supplier and or manufacturer C.R. Klewin Southeast, Inc. will omit the non compliance Trade Contractor from participating in the Owner Direct Purchase program and C.R. Klewin Southeast, Inc. will notify the Owner on a case by case basis.~~
7. Building Department(s) review comments and/or requirements are included as noted on the construction documents listed in the documents section of this report.
8. We assume relocation and/or special construction costs for under/above ground utilities that may be located within the construction limits but not indicated and/or not referenced accurately are not included.
9. We assume that all utilities serving the project are of sufficient capacity and size to provide adequate services without modifications/enhancements.
10. We assume that the project site work hours are from 7:00 a.m. to 7:00 p.m. Monday thru Sunday, or in accordance with city ordinance/regulations.
11. We assume the existing ground conditions will support the proposed construction without soil enhancements, de-mucking and/or special foundation construction, except as specified.

ASSUMPTIONS AND CLARIFICATIONS

Palm Beach Gardens Elementary School

12. We assume that any hazardous materials will be removed and disposed of by the Owner.
13. We assume that any hazardous/unsuitable ground conditions will be removed and replaced with select material by the Owner.
14. We assume that any existing trees/landscaping to be saved/relocated prior to the start of construction will be completed by the Owner prior to the Notice to Proceed with construction.
15. We assume the selection of all building materials and all color selection to be from the specified manufacturers standard building material types and standard colors selections.
16. We assume that electronic (CAD) files will be made available for our use in preparation of shop drawings and coordination drawings at no cost.
17. We have included (3) sets of Playground Equipment at an allowance of \$80,000 each.
18. We assume collateral loads are integral with the design for the suspended floor system and roof systems supporting/accommodating fireproofing construction materials, attachment of all Mechanical/Electrical items and any other construction requiring overhead support.
19. We have included light weight concrete roof insulation as shown on structural drawings in lieu of the rigid polyiso. insulation shown on the architectural drawings.
20. We assume that all interior and exterior cmu is to be stucco block.
21. We have included abuse resistant gypsum wallboard to a height of 8 feet at corridors and multi-purpose room only.
22. We have included stucco on cmu at the exterior face of P.E. building and dumpster enclosure.
23. We have included veneer plaster at corridors and the multipurpose room only.
24. We have assumed "Stucco Finish" noted on elevations to be a "Paint Finish"

ASSUMPTIONS AND CLARIFICATIONS

Palm Beach Gardens Elementary School

25. We have included ASI drawings dated 2/28/07 and these drawings are listed and logged in the documents sections of this report.
26. We have assumed that ASI #1 drawings will be revised as necessary to indicate window widths intended for windows A and B (1 at 40" and 1 at 27")
27. We include the impact of PGAL ASI #1 dated 3/20/07 and JLRD response dated 3/20/07.
28. We include attached to this section copies of PGAL and JLRD ASI #1 instructions and have noted our exclusion of items # 11, 12 and 19 as information in not sufficient for pricing.

Anthony Scippa

From: Kari Botek [KBotek@pgal.com]
Sent: Tuesday, March 20, 2007 5:22 PM
To: Anthony Scippa; Greg Bischof; Jackie Cooper
Cc: Glen Armbruster; crewsr@mail.palmbeach.k12.fl.us
Subject: PBGE - ASI #1 status

Dear Greg / Tony / Jackie:

Here is the updated ASI #1 list.

I am anticipating receipt of the narrative on the electrical items from JLRD by tomorrow morning; I shall forward these as soon as I receive them.

If you have any questions, concerns, or require any additional information, please do not hesitate to let me know.

Sincerely,
Kari

Kari Botek, RA
Senior Associate



2006 Firm of the Year - AIA Houston

Alexandria	Atlanta
[T] 703 836 0588 [F] 703 836 8027	[T] 404 602 3800 [F] 404 602 3810
Boca Raton	Dallas
[T] 561 988 4002 [F] 561 988 3002	[T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale	Houston
[T] 954 527 5001 [F] 954 527 4177	[T] 713 622 1444 [F] 713 968 9333
Las Vegas	Los Angeles
[T] 702 435 4448 [F] 702 435 4470	[T] 310 645 3276 [F] 310 645 3026
Phoenix	
[T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

PALM BEACH GARDENS ELEMENTARY SCHOOL
REPLACEMENT PROJECT **0111-7505**
03.20.07

Architect's Supplemental Instruction #1:

ASI #1 is to contain the following items that may affect the determination of the GMP:

1. At the Multipurpose Room at the southwest corner there is to be an electrical & data connection for the support of a laptop presentation. → JLRD
 2. Electrical provisions for cash registers as recently required by the SDPBC → JLRD
 - ✓ 3. Indicate all 18" deep metal shelving in ESE and material storage rooms to be in-contract.
 4. ESOL designated classroom **Room 2-134**: additional computer usage required (up to 10 computers total) so additional electrical & teledata receptacles for 6 additional computers required at this classroom. → JLRD
 - ✓ 5. Fence heights at retention areas: PGAL to pursue variance to 4' high fencing (in lieu of 6') with SDPBC Bldg Dept. upon approval from SDPBC Risk Management.
 6. Stage: PGAL/JLRD to locate wiring as necessary to support installation of speakers at inside of stage so performers can hear. → JLRD
 - ✓ 7. Production Work Room, Room 1-118, at Administration: a provision for a dishwasher is to be made (in regard to millwork, electrical, plumbing).
 - ✓ 8. Elevations: revisions such that brick inlay to be at entrance points to facility only
 9. Provision of exterior lighting at entry feature → JLRD
 - ✓ 10. Proper coordination with structural drawings such that all toilet rooms indicate required recess for ceramic floor tiles
 - ~~Excluded~~ 11. ~~Civil construction documents responding to SEWMD and Seacoast review comments~~
 - ~~Excluded~~ 12. ~~Resolution of remaining building department comments.~~
 - ✓ 13. Music Storage Room 3-102C: Elimination of Wenger storage cabinets, provide open millwork shelving instead.
 - ✓ 14. Outdoor Stage: Removal of overhead coiling door (#3-104 / 3) from the project.
 - ✓ 15. Provision of cage/fence at Custodial Receiving (Room 3-180).
 - ✓ 16. Provision of 1" fiberglass panels at suspended ceiling of Music Classroom and Multipurpose Room.
 17. Provide additional electrical outlet for music room keyboards. → JLRD
 18. Provide (4) 3" pvc conduits from Control Rm (3-101B) to CCTV Rm.(3-101C). → JLRD
 - ~~Excluded~~ 19. Provide grid lighting at CCTV per School Staff needs. → JLRD
 - ✓ 20. Plumbing is to be provided to Refrigerator (for icemaker) in Clinic (Room 1-124)
- ASI #1 is to contain the following items that should clarify or correct information but should not affect the GMP.
- ✓ 1. Correction of window height at stairwells: sills to be at 42" above landing

- ✓ 2. Correction of sink location at Clinic in the Administration area
- ✓ 3. Coordinate between architectural and electrical reflected ceiling plan at Clinic
- ✓ 4. Relocation of PTA-donated oak tree

Anthony Scippa

From: Kari Botek [KBotek@pgal.com]
Sent: Wednesday, March 21, 2007 11:23 AM
To: Anthony Scippa
Cc: Greg Bischof, Jackie Cooper, Glen Armbruster, crewsr@mail.palmbeach.k12.fl.us
Subject: FW: Palm Beach Gardens EI- ASI #1 - electrical narrative

Dear Tony,

Please see the narrative as provided by JLRD.
 I am still working with him on Item 1 as I need to clarify for him that this was an ADDITIONAL outlet (data and electric) as requested by SDPBC Staff.

I will forward to you the resolution on number 1 asap.

Thanks,
 Kari

From: Ron Levinson [mailto:rlevinson@jlrinc.com]
Sent: Tuesday, March 20, 2007 5:18 PM
To: Kari Botek
Subject: RE: Palm Beach Gardens EI- ASI #1

Kari:

I have reviewed the electrical items and offer the following:

- ✓ 1. Note 20 on Sheet E1-11 already addresses this item. Provisions are made on the stage for the connection of a computer to the projector.
- ✓ 2. Power has been provided for cash registers as shown on Sheet E3-01. The new criteria from the District is for the data raceways for the cash registers to run to the nearest communications closet instead of to the cafeteria managers office. The nearest Data equipment is in room 3-190. These outlets shall be installed in accordance with detail 2/E-4-02 and detail 2/E6-02.
- ✓ 4. Three (3) additional quad outlet will be required in this room for the added computers, one for each group of two computers. Two (2) additional data outlets will be required, one for each group of four computers. Exact location of added computers will affect the actual layout of these devices. The extra circuits may be feed from spare breakers in Panel '2DA1', two quad outlets per circuit maximum.
- ✓ 6. Provide two (2) speakers on the stage, room 3-104, connected to the local sound system. Provide separate volume control for these speakers.
- ✓ 7. Provide duplex receptacle below sink for future dishwasher in Room 1-118. Connect to spare circuit breaker in Panel '1L'.
- ✓ 9. There is currently lighting shown for the entry canopy. I do not know what is requested here.
- ✓ 17. Additional duplex outlets can be provided in the Music Room 3-102 for keyboards, two keyboards per duplex outlet. Confirm quantity and locations. These can be fed from spare breakers in panel '3DB', maximum 4 per circuit.
- ✓ 18. These sleeves are shown as Note 19 on Sheet E1.11.

3/28/2007

19. Provisions have been made for owner furnished lighting fixtures in Room 3-101A. See detail 2/E1-10. ~~If owner desires these fixtures to be included in the contract, they must provide an approved bill of materials.~~

I hope this information is useful to you. If you have any questions or require additional information, please let me know.

THANK YOU,

RON LEVINSON
JOHNSON, LEVINSON, RAGAN, DAVILA, INC.
1450 CENTREPARK BOULEVARD, SUITE 350
WEST PALM BEACH, FLORIDA 33401
PHONE: (561) 689-2303 EXT. 107
FAX: (561) 689-2302
E-MAIL: rlevinson@jlrldinc.com

From: Kari Botek [<mailto:KBotek@pgal.com>]
Sent: Tuesday, March 20, 2007 5:12 PM
To: rlevinson@jlrldinc.com
Subject: Palm Beach Gardens EI- ASI #1

Dear Ron,
Please let me know what narrative you can provide in regard to the ASI items that pertain to you.
Sincerely,
Kari

Kari Botek, RA
Senior Associate



2006 Firm of the Year - AIA Houston

Alexandria	Atlanta
[T] 703 836 0588 [F] 703 836 8027	[T] 404 602 3800 [F] 404 602 3810
Boca Raton	Dallas
[T] 561 988 4002 [F] 561 988 3002	[T] 972 871 2225 [F] 972 871 2228
Fort Lauderdale	Houston
[T] 954 527 5001 [F] 954 527 4177	[T] 713 622 1444 [F] 713 968 9333
Las Vegas	Los Angeles
[T] 702 435 4448 [F] 702 435 4470	[T] 310 645 3276 [F] 310 645 3026
Phoenix	
[T] 602 324 7760 [F] 602 324 7768	http://www.PGAL.com

*** eSafe scanned this email for malicious content ***
*** IMPORTANT: Do not open attachments from unrecognized senders ***

3/28/2007

ASSUMPTIONS AND CLARIFICATIONS

Palm Beach Gardens Elementary School

29. FLORIDA LEAGUE OF CITIES MASTER CONTROLLED INSURANCE PROGRAM (MCIP)

All OSHA and Competent Person training will be provided for all Construction Managers, General Contractors, Contractors and Subcontractors by The School District of Palm Beach County, Florida and / or the administrators of the Florida League of Cities Master controlled Insurance Program, at no cost.

All new hire safety orientations will be scheduled and conducted by The School District of Palm Beach County, Florida and / or the administrators of the Florida League of Cities Master controlled Insurance Program, at no cost.

The School District of Palm Beach County, Florida will provide a badge or numbered hardhat sticker for each person having completed the safety orientation at no cost.

The School District of Palm Beach County, Florida will prepare and maintain a list of all personal that have completed a safety orientation class for cross referencing from one School District of Palm Beach County, Florida project to another School District of Pam Beach County, Florida Project.

The School District of Palm Beach County, Florida will provide assistance to Construction Manager and Subcontractors on how to conduct weekly toolbox safety meetings.

The School District of Palm Beach County, Florida will provide a safety training to all Construction Managers, General Contractors, Contractors and Subcontractors in regard to the specific safety requirements and rules related to the Construction Managers, General Contractors, Contractors and Subcontractors work at no cost.

The School District of Palm Beach County, Florida will provide assistance to all Construction Managers, General Contractors, Contractors and Subcontractors with safety and health inspections at no cost.

The School District of Palm Beach County, Florida will provide drug screening for all Construction Managers, General Contractors, Contractors and Subcontractors for workers that have been with their employer longer than six months and for all new workers at no cost.

The School District of Palm Beach County, Florida will prepare and maintain a list of all personnel that have been drug tested for cross referencing from one SDPBC project to another SDPBC project.

ASSUMPTIONS AND CLARIFICATIONS

Palm Beach Gardens Elementary School

The School District of Palm Beach County, Florida will provide assistance to all Construction Managers, General Contractors, Contractors and Subcontractors on how job hazard analysis are prepared, however will not actually such analysis.

The School District of Palm Beach County, Florida will provide training, orientations, testing / screening, and assistance for all Construction Managers, General Contractors, Contractors and Subcontractors so the project is not delayed.

The School District of Palm Beach County, Florida will assume all administrative duties for the entire Master Controlled Insurance Program to include all required and or related items without exception. C.R. Klewin Southeast, Inc. will provide only minimum administrative assistance.

C.R. Klewin Southeast, Inc. has not included a fulltime Safety Coordinator. Should C.R. Klewin Southeast, Inc. be required to provide a fulltime Safety Coordinator, the additional cost will be \$12,000 per month for each Safety Coordinator with a six month minimum for each Safety Coordinator.

Certain Trade Contractors have included certain administrative costs in their proposals based on their experience with other controlled insurance programs. We have not been able to quantify such costs at this time.

30. COMMISSIONING

We assume that this project will have a commissioning agent and that all commissioning requirements must be followed.

While we have met and discussed a preliminary scope of requirements with the selected agent, to date we do not have a job specific document and therefore have not included any costs whatsoever in our Proposal.

A L L O W A N C E S

Palm Beach Gardens Elementary School

Playground Equipment and Rubberized Play Surface

Three (3) each at \$80,000 = \$240,000

SUMMARY SHEET		PALM BEACH GARDENS G. M. P. ESTIMATE	COMMENTS
DIVISION 2 - SITE CONSTRUCTION		\$ 3,424,748	
DIVISION 3 - CONCRETE		\$ 2,853,156	
DIVISION 4 - MASONRY		\$ 150,516	
DIVISION 5 - STEEL		\$ 1,422,250	
DIVISION 6 - CARPENTRY		\$ 635,600	
DIVISION 7 - THERMAL/MOISTURE		\$ 808,317	
DIVISION 8 - WINDOWS AND DOORS		\$ 982,300	
DIVISION 9 - FINISHES		\$ 2,450,187	
DIVISION 10 - SPECIALTIES		\$ 531,175	
DIVISION 11 - EQUIPMENT		\$ 451,650	
DIVISION 12 - FURNISHINGS		\$ 30,836	
DIVISION 13 - SPECIAL CONSTRUCTION		\$ 99,000	
DIVISION 14 - ELEVATOR		\$ 46,500	
DIVISION 15 - MECHANICAL		\$ 3,365,100	
DIVISION 16 - ELECTRICAL		\$ 2,723,700	
CONSTRUCTION COST SUBTOTAL		\$ 19,975,035	
GENERAL CONDITIONS		\$ 503,460	
CONSTRUCTION PHASE FEE		\$ 995,850	
LIABILITY INSURANCE		\$ 238,365	
BUILDERS RISK INSURANCE		\$ -	By Owner
WIND & STORM INSURANCE		\$ -	By Owner
OVERHEAD & PROFIT		\$ 980,329	
PERFORMANCE & PAYMENT BOND		\$ 197,895	
CONSTRUCTION CONTINGENCY		\$ 600,000	
PRECONSTRUCTION PHASE FEE		\$ 159,539	
SUBTOTAL		\$ 23,650,473	
SALES TAX RECOVERY		\$ (219,725)	
TOTAL		\$ 23,430,747	

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
2002	SITE CONSTRUCTION SURVEY	1.00	LS	\$40,000.00	\$40,000	\$48,000	
	CONSTRUCTION ENGINEERING SURVEYING WORK	1.00	LS	\$8,000.00	\$8,000		
	AS-BUILT DRAWINGS						
2070	BUILDING DEMOLITION					\$271,780	
	BUILDING # 1	3,600	SF	\$4.00	\$14,400		
	BUILDING # 2	3,185	SF	\$4.00	\$12,740		
	BUILDING # 3 & 4	9,842	SF	\$4.00	\$39,368		
	BUILDING # 5 & 6	7,340	SF	\$4.00	\$29,360		
	BUILDING # 7 & 8	9,093	SF	\$4.00	\$36,372		
	BUILDING # 9	7,475	SF	\$4.00	\$29,900		
	BUILDING # 10	7,180	SF	\$4.00	\$28,720		
	BUILDING # 11 COVERED PLAY BUILDING	2,320	SF	\$4.00	\$9,280		
	BUILDING # 12	2,320	SF	\$4.00	\$9,280		
	BUILDING # 14	7,220	SF	\$4.00	\$28,880		
	COVERED WALKWAYS	10,800	SF	\$1.50	\$16,200		
	PORTABLE DEMOLITION 3 ea.	4,320	SF	\$4.00	\$17,280		
2110	SITE CLEARING					\$201,877	
	SITE CLEARING	11.00	ACRES	\$3,000.00	\$33,000		
	CHAIN LINK FENCE @ P/L	2,673	LF	\$3.00	\$8,019		
	CHAIN LINK FENCE @ BICYCLE PARKING	140	LF	\$3.00	\$420		
	CHAIN LINK FENCE @ EAST PARKING	560	LF	\$3.00	\$1,680		
	CHAIN LINK FENCE @ TRANSFORMER	55	LF	\$3.00	\$165		
	CHAIN LINK FENCE @ IRRIGATION	40	LF	\$3.00	\$120		
	CHAIN LINK GATES	6	EA	\$200.00	\$1,200		
	12' CHAIN LINK BACKSTOP	1	EA	\$1,500.00	\$1,500		
	REMOVE 18" CMP EAST	70	LF	\$15.00	\$1,050		
	REMOVE 8" PVC PIPE EAST	117	LF	\$10.00	\$1,170		
	REMOVE 6" DIP PIPE WEST	292	LF	\$10.00	\$2,920		
	REMOVE CONCRETE FLUMES	6	EA	\$100.00	\$600		
	REMOVE PRECAST INLET EAST	1	EA	\$500.00	\$500		
	REMOVE PRECAST INLET WEST	3	EA	\$500.00	\$1,500		
	REMOVE TYPE "D" CURB	1,371	LF	\$3.00	\$4,113		
	REMOVE CONCRETE FLUMES	5	EA	\$100.00	\$500		
	REMOVE CONCRETE WHEELSTOPS	110	EA	\$10.00	\$1,100		
	REMOVE 4" CONCRETE SIDEWALKS ON-SITE WEST	10,275	SF	\$3.00	\$30,825		
	REMOVE 4" CONCRETE SIDEWALKS ON-SITE EAST INT.	9,185	SF	\$3.00	\$27,555		
	REMOVE 4" CONCRETE BICYCLE PARKING	2,400	SF	\$3.00	\$7,200		
	REMOVE EXISTING PLAY COURT NORTH	428	SYD	\$3.00	\$1,284		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	DIVISION 2 - ON SITE CONSTRUCTION						
	REMOVE EXISTING BASKETBALL COURT SOUTH	1,042	SYD	\$3.00	\$3,126		
	REMOVE EXISTING ASP. PAVEMENT @ BUS LOOP	15,878	SYD	\$3.00	\$47,634		
	REMOVE EXISTING ASP. PAVEMENT @ PARENT DROP	2,396	SYD	\$3.00	\$7,188		
	REMOVE EXISTING ASP. PAVEMENT @ E. PARKING	3,976	SYD	\$3.00	\$11,928		
	SAW ASPHALT & CONCRETE	290	SYD	\$2.00	\$580		
	REMOVE PLAYGROUNDS	2	EA	\$2,500.00	\$5,000		
2200	EARTHWORK					\$346,943	
	MOBILIZATION	2.00	EA	\$2,500.00	\$5,000		
	STRIP TOPSOIL BUILDINGS	1,703	CYD	\$3.00	\$5,109		
	STRIP TOPSOIL ASPHALT PAVING	12,678	CYD	\$3.00	\$38,034		
	PROOF-ROLL - BUILDING PADS	11,294	SYD	\$0.30	\$3,388		
	PROOF-ROLLING CHILLER BUILDING	483	SYD	\$0.30	\$145		
	PROOF-ROLLING COVERED PLAY BUILDING	586	SYD	\$0.30	\$176		
	PROOF-ROLLING ONE STORY BUILDING	5,205	SYD	\$0.30	\$1,562		
	PROOF-ROLLING ONE STORY BUILDING	5,020	SYD	\$0.30	\$1,506		
	PROOF-ROLL - ASPHALT PAVEMENT OFF-SITE TURN LANE	394	SYD	\$0.30	\$118		
	PROOF-ROLL - ASPHALT PAVEMENT PARENT DROP ROAD	1,770	SYD	\$0.30	\$531		
	PROOF-ROLL - ASPHALT PAVEMENT EAST PARKING LOT	5,210	SYD	\$0.30	\$1,563		
	PROOF-ROLL - ASPHALT PAVEMENT BUS LOOP	2,616	SYD	\$0.30	\$785		
	PROOF-ROLL - ASPHALT PAVEMENT SERVICE AREA	602	SYD	\$0.30	\$181		
	PROOF-ROLL - ASPHALT PAVEMENT PLAYCOURTS	2,086	SYD	\$0.30	\$626		
	EROSION CONTROL SITE	3,007	LF	\$3.00	\$9,021		
	UNCLASSIFIED EXC. SITE	1,509	CYD	\$5.00	\$7,545		
	UNCLASSIFIED EXC. SITE PLACE & COMPACT	1,509	CYD	\$4.00	\$6,036		
	IMPORT FILL IN PLACE	17,923	CYD	\$12.00	\$215,076		
	STAGE IMPORT FILL IN PLACE	260	CYD	\$15.00	\$3,900		
	PLACE TOPSOIL ON-SITE	4,176	CYD	\$4.00	\$16,704		
	PLACE TOPSOIL OFF-SITE	488	CYD	\$4.00	\$1,952		
	FINISH GRADING ON-SITE	25,058	SYD	\$1.00	\$25,058		
	FINISH GRADING OFF-SITE	2,928	SYD	\$1.00	\$2,928		
2281	TERMITE CONTROL					\$10,515	
	CLASSROOM ONE STORY BUILDING	38,233	SF	\$0.13	\$4,970		
	CLASSROOM TWO STORY BUILDING	41,081	SF	\$0.13	\$5,341		
	P. E. BUILDING	651	SF	\$0.13	\$85		
	CHILLER BUILDING	919	SF	\$0.13	\$119		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
2400	ASPHALT CONCRETE PAVING & BASE					\$470,906	
	1 1/2" ASPHALT PAVEMENT OFF-SITE TURN LANE	394	SYD	\$15.00	\$5,910		
	1 1/2" ASPHALT PAVEMENT SERVICE DRIVE	602	SYD	\$15.00	\$9,030		
	1 1/2" ASPHALT PAVEMENT BUS LOOP	2,616	SYD	\$15.00	\$39,240		
	1 1/2" ASPHALT PAVEMENT PARENT DROP/PARKING	5,360	SYD	\$15.00	\$80,400		
	1 1/2" ASPHALT PAVEMENT PARENT DROP/ROAD	1,770	SYD	\$15.00	\$26,550		
	1 1/2" ASPHALT PAVEMENT PLAY COURTS	2,086	SYD	\$15.00	\$31,290		
	TACK COAT	12,678	SYD	\$0.50	\$6,339		
	8" LIMEROCK DOT BASE SERVICE AREA	607	SYD	\$15.00	\$9,105		
	8" LIMEROCK DOT BASE BUS LOOP	2,616	SYD	\$15.00	\$39,240		
	8" LIMEROCK DOT BASE PARENT DROP/PARKING	5,360	SYD	\$15.00	\$80,400		
	8" LIMEROCK DOT BASE PARENT DROP/ROAD	1,897	SYD	\$15.00	\$28,455		
	8" LIMEROCK DOT BASE OFF-SITE TURN LANE	412	SYD	\$15.00	\$6,180		
	6" LIMEROCK DOT BASE PLAY COURT	2,131	SYD	\$13.00	\$27,703		
	12" STABILIZED SUBGRADE (LBR 40) SERVICE DRIVE	612	SYD	\$4.50	\$2,754		
	12" STABILIZED SUBGRADE (LBR 40) BUS LOOP	2,746	SYD	\$4.50	\$12,357		
	12" STABILIZED SUBGRADE (LBR 40) PARENT DROP/PARKING	5,628	SYD	\$4.50	\$25,326		
	12" STABILIZED SUBGRADE (LBR 40) PARENT DROP/ROAD	2,024	SYD	\$4.50	\$9,108		
	12" STABILIZED SUBGRADE (LBR 40) PLAY COURT	2,176	SYD	\$4.50	\$9,792		
	12" STABILIZED SUBGRADE (LBR 40) OFF-SITE TURN	430	SYD	\$4.50	\$1,935		
	12" STABILIZED SUBGRADE (LBR 40) PLAY COURT	2,176	SYD	\$4.50	\$9,792		
	1 1/2" ASPHALT PATCH SANITARY CROSSINGS	1	EA	\$2,500.00	\$2,500		
	MOBILIZATION	3	EA	\$2,500.00	\$7,500		
2780	PAVERS					\$15,150	
	2" BRICK PAVERS	550	SF	\$10.00	\$5,500		
	1 1/2" SAND BED	550	SF	\$2.00	\$1,100		
	12" STABILIZED SUBGRADE (LBR 40)	61	SYD	\$50.00	\$3,050		
	FILTER CLOTH	550	SF	\$10.00	\$5,500		
2520	SITE CONCRETE					\$402,145	
	5'-0" X 4" CONCRETE SIDEWALKS OFF-SITE EAST	4,530	SF	\$5.50	\$24,915		
	5'-0" X 4" CONCRETE SIDEWALKS OFF-SITE WEST	3,150	SF	\$5.50	\$17,325		
	5'-0" X 4" CONCRETE SIDEWALKS OFF-SITE SOUTH	5,580	SF	\$5.50	\$30,690		
	10' X 4" CONCRETE SIDEWALKS W/ 8' X 12" TOE	250	SF	\$6.00	\$1,500		
	8' X 4" CONCRETE SIDEWALKS W/ 8' X 12" TOE	560	SF	\$6.00	\$3,360		
	6' X 4" CONCRETE SIDEWALKS W/ 8' X 12" TOE	954	SF	\$6.00	\$5,724		
	4' X 6" CONCRETE SIDEWALKS @ CHILLER	459	SF	\$6.00	\$2,754		
	4' X 10' CONCRETE SIDEWALKS @ COVERED PLAY	1,050	SF	\$5.00	\$5,250		
	4' X 8' CONCRETE SIDEWALKS @ SOUTH BUILDING	1,056	SF	\$5.00	\$5,280		

SPEC REF.	DESCRIPTION	DIVISION 2 - ON SITE CONSTRUCTION				SECTION TOTAL	REMARKS
		QUANTITY	UNIT	UNIT COST	TOTAL		
	4" X 6' CONCRETE SIDEWALKS @ SOUTH BUILDING	36	SF	\$5.00	\$180		
	4" X 4' CONCRETE SIDEWALKS @ SOUTH BUILDING	434	SF	\$5.00	\$2,170		
	4" X 10' CONCRETE SIDEWALKS @ SOUTH BUS LOOP	680	SF	\$5.00	\$3,400		
	4" X 6' CONCRETE SIDEWALKS @ SOUTH BUS LOOP	978	SF	\$5.00	\$4,890		
	4" X 10' CONCRETE SIDEWALKS @ SERVICE AREA	960	SF	\$5.00	\$4,800		
	4" X 6' CONCRETE SIDEWALKS @ SERVICE AREA	582	SF	\$5.00	\$2,910		
	4" X 6' CONCRETE SIDEWALKS @ PARENT DROP ENTRANCE	612	SF	\$5.00	\$3,060		
	4" X 6' CONCRETE SIDEWALKS @ PARENT DROP	675	SF	\$5.00	\$3,375		
	4" X 10' CONCRETE SIDEWALKS @ PARKING LOT	300	SF	\$5.00	\$1,500		
	4" X 6' CONCRETE SIDEWALKS @ PARKING LOT	1,710	SF	\$5.00	\$8,550		
	4" X 6' CONCRETE SIDEWALKS @ ENTRANCE ROAD	2,490	SF	\$5.00	\$12,450		
	DETECTABLE WARNING SURFACE STANDARD WALK	24	EA	\$800.00	\$19,200		
	DETECTABLE WARNING SURFACE 20' WIDE WALK	3	EA	\$2,500.00	\$7,500		
	10' X 10' X 4" COURTYARD CONCRETE SIDEWALKS	19,026	SF	\$5.00	\$95,130		
	4" COURTYARD CONCRETE STAGE	489	SF	\$5.00	\$2,445		
	6" X 4" CONCRETE H C RAMP	180	SF	\$5.00	\$900		
	12" CONCRETE STAGE STEPS	215	SF	\$30.00	\$6,450		
	COVERED WALKWAY SIDEWALKS & FOUN. PARENT	4,410	SF	\$10.00	\$44,100		
	COVERED WALKWAY SIDEWALKS & FOUN. BUS	2,880	SF	\$10.00	\$28,800		
	COVERED WALKWAY SIDEWALKS & FOUN. ART	565	SF	\$10.00	\$5,650		
	COVERED WALKWAY SIDEWALKS & FOUN. KINDERGARTEN	440	SF	\$10.00	\$4,400		
	4" SIDEWALK @ ART PATIO	1,636	SF	\$5.00	\$8,180		
	1W-24 FOOTING @ ART PATIO WALL	80	LF	\$55.00	\$4,400		
	8" X 24" WALL @ ART PATIO	80	LF	\$55.00	\$4,400		
	BICYCLE PARKING	1,457	SF	\$5.50	\$8,014		
	6" SOG L. P. GAS TANK PAD	200	SF	\$6.00	\$1,200		
	6" SOG DUMPSTER PAD	300	SF	\$6.00	\$1,800		
	6" R C PAVMENT @ DUMPSTER PAD	250	SF	\$6.00	\$1,500		
	6" SOG ITV TOWER	100	SF	\$6.00	\$600		
	6" SOG CONDENSING UNITS @ KITCHEN	84	SF	\$6.00	\$504		
	6" SOG TRANSFORMER PAD	144	SF	\$6.00	\$864		
	6" SOG IRRIGATION PUMP PAD	64	SF	\$6.00	\$384		
	FLAGPOLE BASE	1	LS	\$600.00	\$600		
	PIPE BOLLARDS	7	LS	\$500.00	\$3,500		
	MARQUEE SIGN - Gen. Constr.	1	EA	\$8,000.00	\$8,000		
2521	CONCRETE CURBS				\$77,148		
	TYPE "F" CURB	0	LF	\$16.00	\$0		
	TYPE "D" CURB @ ENTRANCE ROAD	415	LF	\$17.00	\$7,055		
	TYPE "D" CURB @ SERVICE AREA	128	LF	\$17.00	\$2,176		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	DIVISION 2 - ON SITE CONSTRUCTION						
	TYPE "D" CURB @ BUS LOOP	1,452	LF	\$17.00	\$24,684		
	TYPE "D" CURB @ PARENT DROP	355	LF	\$17.00	\$6,035		
	TYPE "D" CURB @ EAST PARKING	2,144	LF	\$17.00	\$36,448		
	10" X 12" HEADER CURB @ PAVERS	50	LF	\$15.00	\$750		
2580	PAVEMENT MARKINGS					\$25,381	
	H C PARKING	7	EA	\$50.00	\$350		
	REGULAR PARKING	132	EA	\$15.00	\$1,980		
	WHEELSTOPS	139	EA	\$22.00	\$3,058		
	4" DOUBLE YELLOW	410	LF	\$0.60	\$246		
	4" SOLID YELLOW	300	LF	\$0.30	\$90		
	4" SOLID YELLOW DIAGONAL	940	LF	\$0.30	\$282		
	4" RED SOLID LINE	350	LF	\$0.50	\$175		
	10" WIDE CROSSWALK MARKINGS	11	EA	\$300.00	\$3,300		
	12" ARROWS	37	EA	\$50.00	\$1,850		
	24" STOP BARS	11	EA	\$150.00	\$1,650		
	(9) NO PARKING/FIRE LANE R7-201	11	EA	\$200.00	\$2,200		
	(11) ONE WAY R6-2	1	EA	\$200.00	\$200		
	(12) DO NOT ENTER R5-1	4	EA	\$200.00	\$800		
	(13) STOP R1-1	10	EA	\$300.00	\$3,000		
	(14) NO TURN R3-1	1	EA	\$200.00	\$200		
	(16) H C PARKING SIGNS	7	EA	\$200.00	\$1,400		
	(17) PEOPLE WALKING S1-1	5	EA	\$200.00	\$1,000		
	(17a) ARROW W16-7P	5	EA	\$200.00	\$1,000		
	(18) DO NOT BLOCK CROSSWALK (SPECIAL #1)	5	EA	\$300.00	\$1,500		
	(19) TURN ONLY R3-5L	1	EA	\$200.00	\$200		
	(19) SCHOOL BUSES ONLY (SPECIAL #2)	1	EA	\$300.00	\$300		
	(19) DO NOT BLOCK CROSSWALK (SPECIAL #3)	1	EA	\$300.00	\$300		
	BUSES ONLY	1	EA	\$300.00	\$300		
2657	FIRE LINE WATER DISTRIBUTION					\$78,700	
	TIE INTO EXISTING SYSTEM	1	EA	\$3,500.00	\$3,500		
	10" DIP MAIN CLASS 52	50	LF	\$60.00	\$3,000		
	8" DIP MAIN CLASS 52	795	LF	\$40.00	\$31,800		
	6" DIP MAIN CLASS 52	140	LF	\$35.00	\$4,900		
	4" DIP MAIN CLASS 52	20	LF	\$30.00	\$600		
	10" GATE VALVE	1	EA	\$1,500.00	\$1,500		
	8" GATE VALVE	1	EA	\$1,200.00	\$1,200		
	6" GATE VALVE	2	EA	\$900.00	\$1,800		
	10" FITTINGS	2	EA	\$500.00	\$1,000		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	8" FITTINGS	12	EA	\$500.00	\$6,000		
	6" FITTINGS	2	EA	\$400.00	\$800		
	4" FITTINGS	1	EA	\$400.00	\$400		
	8" DOUBLE DETECTOR VALVE	1	EA	\$10,000.00	\$10,000		
	4" POST INDICATOR VALVE	1	EA	\$2,700.00	\$2,700		
	FIRE DEPARTMENT CONNECTION	1	EA	\$2,700.00	\$2,700		
	FIRE HYDRANT ASSEMBLIES	2	EA	\$3,000.00	\$6,000		
	SAMPLE POINTS	4	EA	\$200.00	\$800		
	POTABLE WATER DISTRIBUTION					\$34,720	
	4" DIP MAIN CLASS 52	575	LF	\$28.00	\$16,100		
	4" FITTINGS	7	EA	\$450.00	\$3,150		
	4" GATE VALVE	2	EA	\$250.00	\$500		
	3" DUEL RZP BACKFLOW PREVENTER	1	EA	\$410.00	\$410		
	3" WATER METER BOX	1	EA	\$800.00	\$800		
	3" WATER METER	1	EA	\$2,500.00	\$2,500		
	4" PIPE BOLLARDS @ WATER METER PIT	8	EA	\$500.00	\$4,000		
	2" PVC MAIN TO COVERED PLAY	220	LF	\$18.00	\$3,960		
	2" PVC FITTINGS	2	EA	\$50.00	\$100		
	2" PVC GATE VALVE	1	EA	\$100.00	\$100		
	CHLORINATION AND TESTING	1	EA	\$2,500.00	\$2,500		
	SAMPLE POINTS	3	EA	\$200.00	\$600		
2700	STORM DRAINAGE					\$543,175	
	INLET TYPE C/P	4	EA	\$4,500.00	\$18,000		
	INLET TYPE F/P	6	EA	\$4,800.00	\$28,800		
	INLET TYPE F/J	17	EA	\$5,000.00	\$85,000		
	INLET TYPE G/P	2	EA	\$4,000.00	\$8,000		
	INLET TYPE G/J	3	EA	\$5,500.00	\$16,500		
	TYPE J MANHOLE	4	EA	\$4,000.00	\$16,000		
	24" RCP PIPE	1,625	LF	\$50.00	\$81,250		
	18" RCP PIPE	705	LF	\$40.00	\$28,200		
	15" RCP PIPE	185	LF	\$35.00	\$6,475		
	24" RCP PIPE EX-FILTRATION TRENCH WEST SITE	195	LF	\$120.00	\$23,400		
	24" RCP PIPE EX-FILTRATION TRENCH EAST PARKING	1,475	LF	\$120.00	\$177,000		
	18" RCP PIPE EX-FILTRATION TRENCH	0	LF	\$90.00	\$0		
	ROOF DRAINAGE SYSTEM						
	YARD DRAINS	5	EA	\$250.00	\$1,250		
	10" PVC PIPE	1,070	LF	\$30.00	\$32,100		
	8" PVC PIPE	170	LF	\$25.00	\$4,250		

SPEC REF.	DESCRIPTION	DIVISION 2 - ON SITE CONSTRUCTION				SECTION TOTAL	REMARKS
		QUANTITY	UNIT	UNIT COST	TOTAL		
	6" PVC PIPE	230	LF	\$20.00	\$4,600		
	12" PVC FITTINGS	0	EA	\$125.00	\$0		
	10" PVC FITTINGS	33	EA	\$100.00	\$3,300		
	8" PVC FITTINGS	4	EA	\$75.00	\$300		
	6" PVC FITTINGS	29	EA	\$50.00	\$1,450		
	DOWNSPOUT CONNECTION ASSEMBLIES	29	EA	\$100.00	\$2,900		
	CLEAN-OUTS	22	EA	\$200.00	\$4,400		
	2732 SANITARY SEWER SYSTEM					\$71,890	
	DEWATERING	1	MO	\$5,000.00	\$5,000		
	TIE INTO EXISTING SYSTEM	1	EA	\$3,000.00	\$3,000		
	PRECAST SANITARY MANHOLES	4	EA	\$3,500.00	\$14,000		
	8" SDR 35 PVC MAIN	849	LF	\$30.00	\$25,470		
	6" SDR 35 PVC MAIN	120	LF	\$25.00	\$3,000		
	4" SDR 35 PVC MAIN	90	LF	\$20.00	\$1,800		
	8" SDR 35 PVC FITTINGS	5	EA	\$50.00	\$250		
	6" SDR 35 PVC FITTINGS	2	EA	\$40.00	\$80		
	4" SDR 35 PVC FITTINGS	3	EA	\$30.00	\$90		
	GREASE TRAPS	3	EA	\$6,000.00	\$18,000		
	CLEANOUTS	6	EA	\$200.00	\$1,200		
	2810 IRRIGATION SYSTEM					\$75,000	
	PUMP STATION	1	EA	\$25,000.00	\$25,000		
	CONTROLLERS	1	EA	\$6,000.00	\$6,000		
	IRRIGATION AREAS	11.00	ACRE	\$4,000.00	\$44,000		
	2820 SITE FURNISHINGS					\$4,900	
	GAMETIME # 28006 PVC COATED BENCHES	4	EA	\$250.00	\$1,000		
	BRANDAR RB-11 BIKE RACKS	6	EA	\$650.00	\$3,900		
	2831 CHAIN LINK FENCE & GATES					\$232,382	
	8' GALV-ALUM CHAIN LINK FENCE @ BICYCLE PARKING	0	LF	\$0.00	\$0		
	6' GALV-ALUM CHAIN LINK FENCE @ P/L	0	LF	\$0.00	\$0		
	6' GALV-ALUM CHAIN LINK FENCE @ ITV TOWER	0	LF	\$0.00	\$0		
	6' GALV-ALUM CHAIN LINK FENCE @ COND. UNITS	0	LF	\$0.00	\$0		
	6' GALV-ALUM CHAIN LINK FENCE @ SERVICE AREA	0	LF	\$0.00	\$0		
	6' GALV-ALUM CHAIN LINK FENCE @ NORTH RET. AREA	0	LF	\$0.00	\$0		
	6' GALV-ALUM CHAIN LINK FENCE @ EAST RET. AREA	0	LF	\$0.00	\$0		
	6' GALV-ALUM CHAIN LINK FENCE @ WEST ENT. DRIVE	0	LF	\$0.00	\$0		
	6' GALV-ALUM CHAIN LINK FENCE KINDERGARTEN PLAY AREA	0	LF	\$0.00	\$0		

PALM BEACH GARDENS ELEMENTARY SCHOOL
G. M. P. ESTIMATE

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	
						TOTAL	REMARKS
	DIVISION 2 - ON SITE CONSTRUCTION						
	6' BLACK VINYL COATED CHAIN LINK FENCE @ BICYCLE PARKING	156	LF	\$40.00	\$6,240		
	6' BLACK VINYL COATED CHAIN LINK FENCE @ NORTH P/L	465	LF	\$33.00	\$15,345		
	6' BLACK VINYL COATED CHAIN LINK FENCE @ WEST P/L	575	LF	\$33.00	\$18,975		
	6' BLACK VINYL COATED CHAIN LINK FENCE @ SOUTH P/L	930	LF	\$33.00	\$30,690		
	6' BLACK VINYL COATED CHAIN LINK FENCE @ EAST P/L	675	LF	\$33.00	\$22,275		
	6' BLACK VINYL COATED CHAIN LINK FENCE @ WEST ENT. DRIVE	390	LF	\$33.00	\$12,870		
	6' BLACK VINYL CHAIN LINK FENCE @ ITV TOWER	40	LF	\$33.00	\$1,320		
	6' BLACK VINYL CHAIN LINK FENCE @ REFRIGERATION UNITS	62	LF	\$33.00	\$2,046		
	6' BLACK VINYL CHAIN LINK FENCE @ SERVICE AREA / CHILLER	361	LF	\$33.00	\$11,913		
	6' BLACK VINYL CHAIN LINK FENCE @ IRRIGATION PUMP STA.	54	LF	\$33.00	\$1,782		
	6' BLACK VINYL CHAIN LINK FENCE @ BACKFLOW PREVENTER	65	LF	\$33.00	\$2,145		
	6' BLACK VINYL CHAIN LINK FENCE @ KINDERGARTEN PLAY AREA	223	LF	\$33.00	\$7,359		
	6' BLACK VINYL COATED CHAIN LINK FENCE @ N. RETENTION	255	LF	\$33.00	\$8,415		
	6' BLACK VINYL COATED CHAIN LINK FENCE @ S. LARGE RETENTION	474	LF	\$33.00	\$15,642		
	6' BLACK VINYL COATED CHAIN LINK FENCE @ S. SMALL RETENTION	205	LF	\$33.00	\$6,765		
	16' BLACK VINYL COATED CANTILEVER BACKSTOP	1	EA	\$9,000.00	\$9,000		
	8' X 5' GATES @ BICYCLE PARKING	0	EA	\$0.00	\$0		
	6' X 4' GATES	0	EA	\$0.00	\$0		
	6' X 6' DOUBLE GATES	0	EA	\$0.00	\$0		
	10' X 6' DOUBLE GATES	0	EA	\$0.00	\$0		
	6' X 25' DOUBLE GATES	0	EA	\$0.00	\$0		
	6' X 30' DOUBLE GATES	0	EA	\$0.00	\$0		
	6' X 45' DOUBLE GATES	0	EA	\$0.00	\$0		
	7' X 4' VINYL COATED GATES @ BICYCLE PARKING	2	EA	\$700.00	\$1,400		
	6' X 4' VINYL COATED GATES	6	EA	\$800.00	\$4,800		
	6' X 6' VINYL COATED DOUBLE GATES	2	EA	\$1,000.00	\$2,000		
	6' X 8' VINYL COATED DOUBLE GATES	2	EA	\$1,200.00	\$2,400		
	6' X 10' VINYL COATED DOUBLE GATES	4	EA	\$1,300.00	\$5,200		
	6' X 30' VINYL DOUBLE GATES	5	EA	\$8,000.00	\$40,000		
	DUMPSTER GATE 7' X 10' DOUBLE GATE VINYL COATED SLATS	2	EA	\$1,900.00	\$3,800		
							\$188,414
2950	LANDSCAPING						
369	TREES / PALMS						
	RELOCATE OAK TREE	1	EA	\$800.00	\$800		
	AR RED MAPLE 12' X 6' SPD. 2.5" CAL.	17	EA	\$300.00	\$5,100		
	BS GOMBO LIMBO 14'-16' 4" CAL.	15	EA	\$250.00	\$3,750		
	CL SUGARBERRY 14' X 7' SPD. 3.5" CAL.	4	EA	\$300.00	\$1,200		
	CO SATIN LEAF 12'-14' 2.5" CAL.	10	EA	\$300.00	\$3,000		
	CD PIGEON PLUMB 14' 3" CAL.	12	EA	\$250.00	\$3,000		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	DIVISION 2 - ON SITE CONSTRUCTION						
GES	SILVER BUTOMWOOD 12' X 6' SPD., STANDARD	11	EA	\$300.00	\$3,300		
GL	LOBLOLLY BAY 12' X 5' SPD. 2.5" CAL.	23	EA	\$300.00	\$6,900		
GD	BLOLLY 12' X 6' SPD. 3" CT	4	EA	\$300.00	\$1,200		
KE	GOLDEN RAIN TREE 10'-12' X 4'-5' SPD.	1	EA	\$300.00	\$300		
KF	BLACK IRONWOOD 10' X 3" CT	3	EA	\$300.00	\$900		
LI	GRAPE MYRTLE 12' X 6' SPD. 3" CT	17	EA	\$300.00	\$5,100		
LL	WILD TAMARID 14'-16' 3" CAL.	22	EA	\$300.00	\$6,600		
MC	WAX MYRTLE 12' X 6' SPD. 3" CT	8	EA	\$300.00	\$2,400		
PE	ALEXANDER PALM 12' CT., 13 @ DT & 13' TT	26	EA	\$300.00	\$7,800		
QV	LIVE OAK 14'-16" X 3 1/2" CAL	56	EA	\$250.00	\$14,000		
QP	SABLE PALM 14'-16" CT	75	EA	\$200.00	\$15,000		
SG	PARADISE TREE 12' X 6' SPD. 2.5" CAL.	8	EA	\$300.00	\$2,400		
SS	GLAUCOUS CASSIA 8'-10' X 4' SPD.	7	EA	\$300.00	\$2,100		
TC	GOLDEN TRUMPET TREE 12' X 5' SPD. 2.5" CAL.	7	EA	\$300.00	\$2,100		
TD	BALD CYPRESS 12' X 5' SPD. 2.5" CAL.	35	EA	\$350.00	\$12,250		
UP	DRAKE ELM 14' X 7' SPD. 3" CAL.	8	EA	\$300.00	\$2,400		
	SHRUBS / GROUND COVER						
CHI	COCOPLUM 3 GAL., 24" HT X 20" SP, X 24" OC	290	EA	\$25.00	\$7,250		
FIC	GREEN ISLAND FICUS 3 GAL., 12" HT X 12" SP, X 18" OC	1,740	EA	\$12.00	\$20,880		
FOR	FLORIDA PRIVET 7 GAL., 36" HT X 24" SP, X 30" OC	210	EA	\$12.00	\$2,520		
JAV	WAX JASMINE 3 GAL., 18" HT X 16" SP, X 24" OC	210	EA	\$9.00	\$1,890		
MYR	SIMPSON'S STOPPER 7 GAL., 30" HT X 20" SP, X 30" OC	185	EA	\$9.00	\$1,665		
NEB	BOSTON FERN 1 GAL., 12" HT X 8" SP, X 16" OC	1,935	EA	\$5.00	\$9,675		
PEN	RED PENTAS 3 GAL., 18" HT X 16" SP, X 18" OC	1,065	EA	\$9.00	\$9,585		
PSY	WILD COFFEE 7 GAL., 30" HT X 24" SP, X 30" OC	390	EA	\$7.00	\$2,730		
SER	SAVI PALMETTO 7 GAL., 30" HT X 30" SP, X 4" OC	25	EA	\$12.00	\$300		
SPA	SAND CORDGRASS 3 GAL., 24" HT X 24" SP, X 30" OC	730	EA	\$12.00	\$8,760		
STA	NAITAVE BLUE PORTER 3 GAL., 24" HT X 18" SP, X 24" OC	1,215	EA	\$5.00	\$6,075		
TRD	FAKAHATCHEE GRASS 3 GAL., 24" HT X 24" SP, X 30" OC	165	EA	\$12.00	\$1,980		
TRF	DWF FAKAHATCHEE GRASS 3 GAL., 24" HT X 24" SP, X 30" OC	250	EA	\$12.00	\$3,000		
	VINE						
	TRIVARIEGATED BOWER PLANT 3 GAL., X 5'-0" OC	42	EA	\$12.00	\$504		
	3" SHRADED MELALUECA MULCH	200	CYD	\$50.00	\$10,000		
2932	GRASS SODDING					\$47,790	
	BAHIA SOD SITE	205,952	SF	\$0.20	\$41,190		
	BAHIA SOD EAST OFF-SITE	9,748	SF	\$0.20	\$1,950		
	BAHIA SOD SOUTH OFF-SITE	19,725	SF	\$0.20	\$3,945		
	BAHIA SOD WEST OFF-SITE	3,525	SF	\$0.20	\$705		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
2999	SITE RECREATIONAL EQUIPMENT					\$277,933	
	DIVISION 2 - ON-SITE CONSTRUCTION						
	CALIFORNIA PLEXIPAVE COATING	20,555	SF	\$0.60	\$12,333		
	PLAY COURT STRIPING	2	LS	\$2,500.00	\$5,000		
	VOLLEYBALL SLEEVES	2	EA	\$300.00	\$600		
	BASKETBALL EQUIPMENT	8	EA	\$2,500.00	\$20,000		
	PLAYGROUND EQUIPMENT & RUBBERIZED PLAY AREA ALLOWANCE	3	EA	\$80,000.00	\$240,000		
	TOTAL DIVISION 2 SITEWORK				\$3,424,748	\$3,424,748	

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
3200	CONCRETE REINFORCING					\$81,389	
	Welded Wire Mesh, SOG One Story Building	45,202	SF	\$0.25	\$11,301		
	Welded Wire Mesh, SOG Two Story Building	41,932	SF	\$0.25	\$10,483		
	Welded Wire Mesh SOG, Covered Play Building	4,320	SF	\$0.25	\$1,080		
	Welded Wire Mesh SOG, Chiller Building/Enclosure	3,394	SF	\$0.25	\$849		
	Welded Wire Mesh, Suspended Slab	41,060	SF	\$0.25	\$10,265		
	Reinforcing Steel - Material - Strip Footings	17.29	TN	\$900.00	\$15,561		
	Reinforcing Steel - Material - Individual Footings	14.25	TN	\$900.00	\$12,825		
	Reinforcing Steel - Material - Columns	1.36	TN	\$900.00	\$1,224		
	Reinforcing Steel - Material - Beams	2.22	TN	\$900.00	\$1,998		
	Reinf. Steel for Tilt-Up Wall Panels	0.00	TN	\$900.00	\$0		DIV 3 in 3470
	Reinforcing Steel - Labor	35.12	TN	\$450.00	\$15,804		
3300	CAST IN PLACE CONCRETE						
	CONTINUOUS FOOTINGS					\$204,432	
	WF 24 (2'-0" X 1'-0" X 4.7 LF) 8" CMU Dumpster Walls.	4	CYD	\$135.00	\$540		3/A1.05
	Forms	94	SF	\$5.00	\$470		
	Pllace Concrete	4	CYD	\$30.00	\$120		
	Finish & Cure Concrete	94	SF	\$2.00	\$188		
	Rub & Touch-Up	94	SF	\$1.00	\$94		
	Excavation & Fine Grade	17	CYD	\$12.00	\$204		
	Backfill	13	CYD	\$8.00	\$104		
	WF 24 (2'-0" X 1'-0" X 130 LF) 8" CMU Covered Play Building.	10	CYD	\$135.00	\$1,350		
	Forms	260	SF	\$5.00	\$1,300		
	Pllace Concrete	10	CYD	\$30.00	\$300		
	Finish & Cure Concrete	260	SF	\$2.00	\$520		
	Rub & Touch-Up	260	SF	\$1.00	\$260		
	Excavation & Fine Grade	72	CYD	\$12.00	\$864		
	Backfill	62	CYD	\$8.00	\$496		
	WF 24 (2'-0" X 1'-0" X 136 LF) 8" CMU Chiller Building	10	CYD	\$135.00	\$1,350		
	Forms	272	SF	\$5.00	\$1,360		
	Pllace Concrete	10	CYD	\$30.00	\$300		
	Finish & Cure Concrete	272	SF	\$2.00	\$544		
	Rub & Touch-Up	272	SF	\$1.00	\$272		
	Excavation & Fine Grade	76	CYD	\$12.00	\$912		
	Backfill	66	CYD	\$8.00	\$528		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	WF 16 (1'-4" X 1'-0" X 164 LF) 8" CMU One Story Building	9	CYD	\$135.00	\$1,215		
	Forms	328	SF	\$5.00	\$1,640		
	Place Concrete	9	CYD	\$30.00	\$270		
	Finish & Cure Concrete	218	SF	\$2.00	\$436		
	Rub & Touch-Up	328	SF	\$1.00	\$328		
	Excavation & Fine Grade	79	CYD	\$12.00	\$948		
	Backfill	70	CYD	\$8.00	\$560		
	WF 24 (2'-0" X 1'-0" X 88 LF) 8" CMU One Story Building	7	CYD	\$135.00	\$945		
	Forms	176	SF	\$5.00	\$880		
	Place Concrete	7	CYD	\$30.00	\$210		
	Finish & Cure Concrete	176	SF	\$2.00	\$352		
	Rub & Touch-Up	176	SF	\$1.00	\$176		
	Excavation & Fine Grade	49	CYD	\$12.00	\$588		
	Backfill	42	CYD	\$8.00	\$336		
	WF 36 (3'-0" X 1'-2" X 1656 LF) One Story Building	2	CYD	\$135.00	\$270		
	Forms	3,875	SF	\$5.00	\$19,375		
	Place Concrete	216	CYD	\$30.00	\$6,480		
	Finish & Cure Concrete	4,968	SF	\$2.00	\$9,936		
	Rub & Touch-Up	3,875	SF	\$1.00	\$3,875		
	Excavation & Fine Grade	744	CYD	\$12.00	\$8,928		
	Backfill	528	CYD	\$8.00	\$4,224		
	WF36 (3'-0" X 1'-2" X 2100 LF) Story Building	273	CYD	\$135.00	\$36,855		
	Forms	4,914	SF	\$5.00	\$24,570		
	Place Concrete	273	CYD	\$30.00	\$8,190		
	Finish & Cure Concrete	9,300	SF	\$2.00	\$18,600		
	Rub & Touch-Up	4,914	SF	\$1.00	\$4,914		
	Excavation & Fine Grade	1,479	CYD	\$12.00	\$17,748		
	Backfill	1,206	CYD	\$8.00	\$9,648		
	WF48 (4'-0" X 1'-4" X 136 LF) 8" CMU Chiller Building	27	CYD	\$135.00	\$3,645		
	Forms	362	SF	\$5.00	\$1,810		
	Place Concrete	27	CYD	\$30.00	\$810		
	Finish & Cure Concrete	544	SF	\$2.00	\$1,088		
	Rub & Touch-Up	362	SF	\$1.00	\$362		
	Excavation & Fine Grade	118	CYD	\$12.00	\$1,416		
	Backfill	91	CYD	\$8.00	\$728		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
3300	INDIVIDUAL FOOTINGS					\$144,616	
F5.5	5'-0" X 5'-0" X 1'-2" (1 EA) -One Story Bld'g.	2	CYD	\$135.00	\$270		
	Forms	24	SF	\$5.00	\$120		
	Place Concrete	2	CYD	\$30.00	\$60		
	Finish & Cure Concrete	25	SF	\$2.00	\$50		
	Rub & Touch Up	24	SF	\$1.00	\$24		
	Excavation and Fine Grade	8	CYD	\$12.00	\$96		
	Backfill	6	CYD	\$8.00	\$48		
F6.6	6'-0" X 6'-0" X 2'-0" (8 EA) -Covered Play Bld'g.	22	CYD	\$135.00	\$2,970		
	Forms	384	SF	\$5.00	\$1,920		
	Place Concrete	22	CYD	\$30.00	\$660		
	Finish & Cure Concrete	288	SF	\$2.00	\$576		
	Rub & Touch Up	384	SF	\$1.00	\$384		
	Excavation and Fine Grade	96	CYD	\$12.00	\$1,152		
	Backfill	74	CYD	\$8.00	\$592		
F6.12	6'-0" X 14'-6" X 2'-0" (1 EA) -One Story Bld'g.	7	CYD	\$135.00	\$945		
	Forms	82	SF	\$5.00	\$410		
	Place Concrete	7	CYD	\$30.00	\$210		
	Finish & Cure Concrete	87	SF	\$2.00	\$174		
	Rub & Touch Up	82	SF	\$1.00	\$82		
	Excavation and Fine Grade	24	CYD	\$12.00	\$288		
	Backfill	17	CYD	\$8.00	\$136		
F6.6	6'-0" X 6'-0" X 2'-0" (7 EA) -Two Story Bld'g.	19	CYD	\$135.00	\$2,565		
	Forms	336	SF	\$5.00	\$1,680		
	Place Concrete	19	CYD	\$30.00	\$570		
	Finish & Cure Concrete	252	SF	\$2.00	\$504		
	Rub & Touch Up	336	SF	\$1.00	\$336		
	Excavation and Fine Grade	84	CYD	\$12.00	\$1,008		
	Backfill	65	CYD	\$8.00	\$520		
F7.7	7'-0" X 7'-0" X 2'-0" (1 EA) -One Story Bld'g.	4	CYD	\$135.00	\$540		
	Forms	56	SF	\$5.00	\$280		
	Place Concrete	4	CYD	\$30.00	\$120		
	Finish & Cure Concrete	49	SF	\$2.00	\$98		
	Rub & Touch Up	56	SF	\$1.00	\$56		
	Excavation and Fine Grade	15	CYD	\$12.00	\$180		
	Backfill	11	CYD	\$8.00	\$88		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	DIVISION 3 - CONCRETE						
F7.7A	7'-0" X 7'-0" X 3'-0" (2 EA) -One Story Bld'g.	12	CYD	\$135.00	\$1,620		
	Forms	168	SF	\$5.00	\$840		
	Place Concrete	12	CYD	\$30.00	\$360		
	Finish & Cure Concrete	98	SF	\$2.00	\$196		
	Rub & Touch Up	168	SF	\$1.00	\$168		
	Excavation and Fine Grade	38	CYD	\$12.00	\$456		
	Backfill	26	CYD	\$8.00	\$208		
F7.7	7'-0" X 7'-0" X 2'-0" (31 EA) -Two Story Bld'g.	113	CYD	\$135.00	\$15,255		
	Forms	1,736	SF	\$5.00	\$8,680		
	Place Concrete	113	CYD	\$30.00	\$3,390		
	Finish & Cure Concrete	1,519	SF	\$2.00	\$3,038		
	Rub & Touch Up	1,736	SF	\$1.00	\$1,736		
	Excavation and Fine Grade	459	CYD	\$12.00	\$5,508		
	Backfill	346	CYD	\$8.00	\$2,768		
F8.8	12'-0" X 6'-0" X 2'-0" (8 EA) -Two Story Bld'g.	43	CYD	\$135.00	\$5,805		
	Forms	576	SF	\$5.00	\$2,880		
	Place Concrete	43	CYD	\$30.00	\$1,290		
	Finish & Cure Concrete	476	SF	\$2.00	\$952		
	Rub & Touch Up	576	SF	\$1.00	\$576		
	Excavation and Fine Grade	160	CYD	\$12.00	\$1,920		
	Backfill	117	CYD	\$8.00	\$936		
F9.9	9'-0" X 9'-0" X 3'-0" (8 EA) -One Story Bld'g.	72	CYD	\$135.00	\$9,720		
	Forms	864	SF	\$5.00	\$4,320		
	Place Concrete	72	CYD	\$30.00	\$2,160		
	Finish & Cure Concrete	648	SF	\$2.00	\$1,296		
	Rub & Touch Up	864	SF	\$1.00	\$864		
	Excavation and Fine Grade	214	CYD	\$12.00	\$2,568		
	Backfill	145	CYD	\$8.00	\$1,160		
F10.10	10'-0" X 10'-0" X 3'-0" (7 EA) -One Story Bld'g.	78	CYD	\$135.00	\$10,530		
	Forms	840	SF	\$5.00	\$4,200		
	Place Concrete	78	CYD	\$30.00	\$2,340		
	Finish & Cure Concrete	700	SF	\$2.00	\$1,400		
	Rub & Touch Up	840	SF	\$1.00	\$840		
	Excavation and Fine Grade	219	CYD	\$12.00	\$2,628		
	Backfill	141	CYD	\$8.00	\$1,128		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	DIVISION 3 - CONCRETE						
	F12.12 12'-0" X 12'-0" X 3'-0" (3 EA) -One Story Bldg. Forms	48	CYD	\$135.00	\$6,480		
	Place Concrete	432	SF	\$5.00	\$2,160		
	Finish & Cure Concrete	48	CYD	\$30.00	\$1,440		
	Rub & Touch Up	432	SF	\$2.00	\$864		
	Excavation and Fine Grade	432	SF	\$1.00	\$432		
	Backfill	125	CYD	\$12.00	\$1,500		
		77	CYD	\$8.00	\$616		
	Elevator Pit Foundation 13'-0" X 12'-0" X 2'-0" Forms	12	CYD	\$135.00	\$1,620		
	Place Concrete	100	SF	\$5.00	\$500		
	Finish & Cure Concrete	12	CYD	\$30.00	\$360		
	Rub & Touch Up	156	SF	\$2.00	\$312		
	Excavation and Fine Grade	100	SF	\$1.00	\$100		
	Backfill / Dispose	54	CYD	\$12.00	\$648		
		43	CYD	\$8.00	\$344		
	Site Door Wall Foundation 4'-0" X 4'-0" X 1'-0" (12 ea) Forms	8	CYD	\$135.00	\$1,080		
	Place Concrete	192	SF	\$5.00	\$960		
	Finish & Cure Concrete	8	CYD	\$30.00	\$240		
	Rub & Touch Up	192	SF	\$2.00	\$384		
	Excavation and Fine Grade	192	SF	\$1.00	\$192		
	Backfill / Dispose	50	CYD	\$12.00	\$600		
		42	CYD	\$8.00	\$336		
	CONCRETE WALLS / ELEVATOR PIT					\$1,192	
3300	Elevator Pit walls 2'-0" X 8'-0" X 9'-0 X 0'-8" Forms	2	CYD	\$135.00	\$270		Tilt-Up
	Place Concrete	136	SF	\$5.00	\$680		
	Finish & Cure Concrete	2	CYD	\$30.00	\$60		
	Rub & Touch Up	23	SF	\$2.00	\$46		
		136	SF	\$1.00	\$136		
	SLAB ON GRADE					\$426,151	
	5" SOG One Story Building (590 cy)	37,669	SF	\$3.75	\$141,259		
	5" SOG Two Story Building (584 cy)	34,944	SF	\$3.75	\$131,040		
	4" SOG Covered Play Building (8 cy)	600	SF	\$4.00	\$2,400		
	4" SOG Covered Play Building W/12" x 24" TE (37 cy)	3,000	SF	\$4.00	\$12,000		
	4" SOG Chiller Building (10 cy)	822	SF	\$3.75	\$3,083		
	6" SOG Chiller Enclosure (38 cy)	2,006	SF	\$4.00	\$8,024		
	8" x 18" x 9'-0" Chiller Foundations (10 EA)	4	CYD	\$300.00	\$1,200		

SPEC REF.	DESCRIPTION	SECTION				REMARKS
		QUANTITY	UNIT	UNIT COST	TOTAL	
	DIVISION 3 - CONCRETE					
	18" x 36" x 5'-0" Chiller Pump Foundations (2 EA)	2	CYD	\$300.00	\$600	
	6" SOG Equipment Pads	16	CYD	\$300.00	\$4,800	
	Stage Steps	110	SF	\$30.00	\$3,300	
	Sand Fill @ Stags Area	176	CYD	\$22.00	\$3,872	
	Fine Grade	79,041	SF	\$1.00	\$79,041	
	6 Mil Vapor Barrier	94,850	SF	\$0.15	\$14,228	
	TE-24 Thickened Edge @ Covered Play 172 lf.	11	CYD	\$150.00	\$1,650	
	12" x 16" Thickened Edge (TE) @ P. E. Building	21	CYD	\$150.00	\$3,150	
	8" x 8" Thickened Edge (TE) @ Buildings	15	CYD	\$150.00	\$2,250	
	TS-24 Slab @ Chiller Building 42 lf.	3	CYD	\$150.00	\$450	
	TS-6" Slab @ Chillers 440 sf.	9	CYD	\$150.00	\$1,350	
	12" x 24" Thickened Slab (TS) @ Buildings	6	CYD	\$150.00	\$900	
	Termite Control	77,035	SF	\$0.15	\$11,555	
3300	CONCRETE COLUMNS					\$26,768
	C-4 8" X 24" X 56 LF 4 EA Covered Play	3	CYD	\$135.00	\$405	
	Forms	300	SF	\$15.00	\$4,500	
	Place & Finish	3	CYD	\$55.00	\$165	
	Rub & Touch Up	300	SF	\$1.00	\$300	
	C-4 8" X 24" X 32 LF 2 EA Chiller Building	2	CYD	\$135.00	\$270	
	Forms	171	SF	\$15.00	\$2,565	
	Place & Finish	2	CYD	\$55.00	\$110	
	Rub & Touch Up	171	SF	\$1.00	\$171	
	C-9 12" X 12" X 64 LF 4 EA Chiller Building	3	CYD	\$135.00	\$405	
	Forms	256	SF	\$15.00	\$3,840	
	Place & Finish	3	CYD	\$55.00	\$165	
	Rub & Touch Up	256	SF	\$1.00	\$256	
	C-16 16" X 16" X 120 LF 12 EA Site Door Wall Columns	7	CYD	\$135.00	\$945	
	Forms	638	SF	\$15.00	\$9,570	
	Place & Finish	7	CYD	\$55.00	\$385	
	Rub & Touch Up	638	SF	\$1.00	\$638	
	TC-1 8" X 16" X 22 LF 1 EA Kitchen	1	CYD	\$135.00	\$135	
	Forms	118	SF	\$15.00	\$1,770	
	Place & Finish	1	CYD	\$55.00	\$55	
	Rub & Touch Up	118	SF	\$1.00	\$118	

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
3300	CONCRETE BEAMS					\$29,923	
	CB-1 Beam (12" X 16" x 134LF) Chiller Enclosure	7	CYD	\$135.00	\$945		
	Forms	356	SF	\$15.00	\$5,340		
	Place & Finish	7	CYD	\$55.00	\$385		
	Finish & Cure Concrete	134	SF	\$1.00	\$134		
	Rub & Touch Up	356	SF	\$1.00	\$356		
	Shoring	8	SF	\$10.00	\$80		
	CB-16 Beam (16" X 16" x 58 LF) Site Door Walls 12 ea	4	CYD	\$135.00	\$540		
	Forms	232	SF	\$15.00	\$3,480		
	Place & Finish	4	CYD	\$55.00	\$220		
	Finish & Cure Concrete	77	SF	\$1.00	\$77		
	Rub & Touch Up	232	SF	\$1.00	\$232		
	Shoring	66	SF	\$10.00	\$660		
	TB-2 Beam (8" X 16" x 175LF) Chiller Building	6	CYD	\$135.00	\$810		
	Forms	466	SF	\$15.00	\$6,990		
	Place & Finish	6	CYD	\$55.00	\$330		
	Finish & Cure Concrete	117	SF	\$1.00	\$117		
	Rub & Touch Up	466	SF	\$1.00	\$466		
	Shoring	16	SF	\$10.00	\$160		
	TB-1 Beam (8" X 12" x 146LF) Covered Play Building	4	CYD	\$135.00	\$540		
	Forms	292	SF	\$15.00	\$4,380		
	Place & Finish	4	CYD	\$55.00	\$220		
	Finish & Cure Concrete	98	SF	\$1.00	\$98		
	Rub & Touch Up	292	SF	\$1.00	\$292		
	Shoring	10	SF	\$10.00	\$100		
	CC-1 Cap (8" X 8" x 118 LF) Covered Play Building @ 114	2	CYD	\$135.00	\$270		
	Forms	157	SF	\$15.00	\$2,355		
	Place & Finish	2	CYD	\$55.00	\$110		
	Finish & Cure Concrete	79	SF	\$1.00	\$79		
	Rub & Touch Up	157	SF	\$1.00	\$157		
	Shoring	0	SF	\$10.00	\$0		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
3300	SUSPENDED SLABS					\$223,762	
	6 1/2" Slab on 2" Composite Metal Deck, 2nd Floor - Conc. Mat. I	583	CYD	\$135.00	\$78,705		
	Forms	90	SF	\$15.00	\$1,350		
	Place & Finish	34,216	SF	\$1.50	\$51,324		
	Cure Concrete	34,216	SF	\$0.20	\$6,843		
	Shoring Suspended Slab	34,216	SF	\$2.50	\$85,540		
3300	METAL PAN STAIRS & LANDINGS (3 EA)					\$12,270	
	Concrete - 2" Pan Stairs	4	CYD	\$135.00	\$540		
	Concrete - 4" Pan Stairs Landings	6	CYD	\$135.00	\$810		
	Place Concrete	10	CYD	\$850.00	\$8,500		
	Finish & Cure	968	SF	\$2.50	\$2,420		
3470	7 1/2" TILT-UP WALLS (105,563 GROSS SF)					\$1,702,653	
	Engineering Drawings	184	PANEL	\$150.00	\$27,600		
	One Story Building 12' Exterior Walls 30' high	1,568	SF	\$15.00	\$23,520		
	One Story Building 7 1/2" Exterior Walls 30' high	1,508	SF	\$11.00	\$16,588		
	One Story Building 7 1/2" Exterior Walls 27' high	23,688	SF	\$9.50	\$225,036		
	One Story Building 7 1/2" Interior Walls	22,476	SF	\$9.50	\$213,522		
	Two Story Building 7 1/2" Exterior Walls 37' high	15,508	SF	\$13.00	\$201,604		
	Two Story Building 7 1/2" Exterior Walls 35' high	26,803	SF	\$13.00	\$348,439		
	Two Story Building 7 1/2" Exterior Walls 21' high	5,336	SF	\$9.50	\$50,692		
	Two Story Building 7 1/2" Interior Walls	8,676	SF	\$9.50	\$82,422		
	Thin Brick Form Liner for Tilt-Up Panels	3,520	SF	\$3.00	\$10,560		
	Thin Brick Material for Tilt-Up Panels	3,520	SF	\$5.00	\$17,600		
	Thin Brick Labor to install for Tilt-Up Panels	3,520	SF	\$6.00	\$21,120		
	Reinforcing Steel for Tilt-Up Panels	273	TONS	\$900.00	\$245,700		
	Non-Shrink Grout Pockets 8" X 8" X 5 1/2" (536 ea.)	111	CFT	\$150.00	\$16,650		
	1 1/2" Non-Shrink Grout (3757 lf)	104	CYD	\$150.00	\$15,600		
	Welding Panel To Panel	1	LS	\$50,000.00	\$50,000		
	Temporary Casting Bed	26,000	SF	\$3.00	\$78,000		
	150 Ton Crane	5	WK	\$9,000.00	\$45,000		
	Crane Mobilization	2	EA	\$6,500.00	\$13,000		
	TOTAL DIVISION 3 - CONCRETE				\$2,853,156	\$2,853,156	

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
4100	MORTAR AND GROUT					\$37,450	
	Mortar						
	12" Filled Cells	26	CY	\$350.00	\$9,100		
	8" Filled Cells One Story Building	30	CY	\$350.00	\$10,500		
	8" Filled Cells Two Story Building	16	CY	\$350.00	\$5,600		
	8" Filled Cells Chiller Building	11	CY	\$350.00	\$3,850		
	8" Filled Cells Covered Play Building	5	CY	\$350.00	\$1,750		
	8" Filled Cells @ Dumpster	1	CY	\$350.00	\$350		
	8" Concrete Bond Beams	18	CY	\$350.00	\$6,300		
4300	UNIT MASONRY					\$105,596	
	12" Stucco Block Chiller Yard Enclosure Wall	2,304	ea	\$11.00	\$25,344		
	8" Stucco Block Chiller Building Exterior Walls	2,592	ea	\$9.75	\$25,272		
	8" Stucco Block Chiller Building Interior Walls	594	ea	\$9.75	\$5,792		
	8" Stucco Block Covered Play Building Exterior Walls	1,848	ea	\$9.75	\$18,018		
	8" Stucco Block Covered Play Building Interior Walls	324	ea	\$9.75	\$3,159		
	8" Stucco Block One Story Bldg Kitchen Wall	330	ea	\$9.75	\$3,218		
	8" Stucco Block One Story Bldg Kitchen N. Ent.	308	ea	\$9.75	\$3,003		
	8" Stucco Block One Story Bldg Misc. Underground.	100	ea	\$9.75	\$975		
	8" Stucco Block at Dumpster	555	ea	\$9.75	\$5,411		
	8" Stucco Block at 3 ea. Stair Wells	1,500	ea	\$9.75	\$14,625		
	4" Solid Block at 3 ea Stair Wells	80	ea	\$9.75	\$780		
4340	REINFORCING STEEL					\$7,470	
	#5 Steel Reinforcing for Masonry Footing Dowels	2	tn	\$900.00	\$2,070		
	#5 Vertical Reinforcing for Masonry Walls	5	tn	\$900.00	\$4,500		
	#5 Horizontal Reinforcing for Masonry Walls	1	tn	\$900.00	\$900		
	TOTAL DIVISION 4 - MASONRY				\$150,516	\$150,516	

SPEC. REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
5120	STRUCTURAL STEEL					\$877,179	
	6" Steel Bollards 8 EA	0.50	tn	\$1,700.00	\$850		
	One Story Building						
	W 30 X 116 Beams	8.81	tn	\$1,700.00	\$14,977		
	W 24 X 131 Beams	7.99	tn	\$1,700.00	\$13,583		
	W 24 X 117 Beams	15.44	tn	\$1,700.00	\$26,248		
	W 21 X 62 Beams	6.94	tn	\$1,700.00	\$11,798		
	W 12 X 45 Beams	1.88	tn	\$1,700.00	\$2,856		
	HSS 6" X 6" X 1/2" Tube Steel	9.32	tn	\$1,700.00	\$15,844		
	4" X 4" X 1/4" Roof Angle	8.22	tn	\$1,700.00	\$13,974		
	2493 LF				\$20,580		
	3/4" X 6" Expansion Bolts Roof Angle	1,372	ea	\$15.00	\$20,580		
	23 ea	0.31	tn	\$1,700.00	\$527		
	3/4" X 10" X 13" Column Top Plates	0.08	tn	\$1,700.00	\$136		
	1" X 14" X 14" Base Plates	0.9	tn	\$1,700.00	\$1,547		
	1" X 18" X 18" Base Plates	12.0	ea	\$40.00	\$480		
	3/4" X 12" Anchor Bolts, Nuts, Washers	80.0	ea	\$40.00	\$3,200		
	1 1/4" X 24" Anchor Bolts, Nuts, Washers	9.0	cft	\$150.00	\$1,350		
	2" Non shrink Grout	50.0	lf	\$100.00	\$5,000		
	2" Expansion Joint	1.0	ls	\$3,000.00	\$3,000		
	Support for Kitch. Exhaust Hood						
	Titwall Embeds						
	3/4" X 10" X 30" Beam Panel Connection Embed	4 ea	tn	\$1,700.00	\$221		
	3/4" X 10" X 24" Beam Panel Connection Embed	6 ea	tn	\$1,700.00	\$272		
	3/4" X 10" X 21" Beam Panel Connection Embed	6 ea	tn	\$1,700.00	\$238		
	3/4" X 10" X 18" Beam Panel Connection Embed	4 ea	tn	\$1,700.00	\$136		
	5/8" X 10" X 10" Panel Embed Plates	300 ea	tn	\$1,700.00	\$5,967		
	1/2" X 6" X 14" Panel Connection Plates	150 ea	tn	\$1,700.00	\$1,513		
	1/2" X 6" X 8" Joist Pocket Embed Plates	221 ea	tn	\$1,700.00	\$1,275		
	1/4" X 4" X 4" Joist Embed Plates	221 ea	tn	\$1,700.00	\$204		
	1/2" X 4" X 12" Angle Panel Base Connections	150 ea	tn	\$1,700.00	\$391		
	1/2" X 4" X 4" X 8" Panel Angle Connections	72 ea	tn	\$1,700.00	\$272		
	3/4" X 7" X 24" Footing Embed Plates	2.68	tn	\$1,700.00	\$4,556		
	3/4" X 4" Expansion Bolts Footing Wall Panels	300.0	ea	\$20.00	\$6,000		
	Total Embeds	8.85	tn				
	Miscellaneous	6.00	tn	\$1,700.00	\$10,200		
	Erection	66.00	tn	\$800.00	\$52,800		
	Two Story Building						
	W 30 X 99 Beams	1.48	tn	\$1,700.00	\$2,516		
	W 24 X 84 Beams	34.69	tn	\$1,700.00	\$58,973		
	W 21 X 50 Beams	72.87	tn	\$1,700.00	\$123,879		

SPEC REF.	DESCRIPTION DIVISION 5 - STEEL	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	W 18 X 55 Beams	78 LF	tn	\$1,700.00	\$3,638		
	W 18 X 40 Beams	1053 LF	tn	\$1,700.00	\$35,802		
	W 16 X 40 Beams	215 LF	tn	\$1,700.00	\$7,310		
	W 16 X 31 Beams	505 LF	tn	\$1,700.00	\$13,294		
	W 12 X 45 Beams	60 LF	tn	\$1,700.00	\$2,295		
	HSS 6" X 6" X 1/2" Tube Steel 1st Floor	644 LF	tn	\$1,700.00	\$19,278		
	HSS 6" X 6" X 1/2" Tube Steel 2nd Floor	633 LF	tn	\$1,700.00			
	6" X 6" X 3/8" Floor Angle	2222 LF	tn	\$1,700.00	\$28,135		
	4" X 4" X 1/4" Roof Angle	2680 LF	tn	\$1,700.00	\$15,028		
	3/4" X 10" X 13" Column Top Plates	92 EA	tn	\$1,700.00	\$1,989		
	3/4" X 4" Expansion Bolts Roof Angle	1,474.0 ea	ea	\$20.00	\$29,480		
	3/4" X 4" Expansion Bolts Floor Angle	1,222.0 ea	ea	\$20.00	\$24,440		
	1" x 14" x 14" Base Plates	46 EA	tn	\$1,700.00	\$2,159		
	3/4" X 12" Anchor Bolts, Nuts, Washers	184.0 ea	ea	\$40.00			
	2" Non shrink Grout	11.0 cft	cft	\$150.00	\$1,650		
	2" Expansion Joint	76.0 lf	lf	\$100.00	\$7,600		
	Tiltwall Embeds						
	3/4" X 10" X 30" Beam Panel Connection Embed	2 ea	tn	\$1,700.00	\$102		
	3/4" X 10" X 24" Beam Panel Connection Embed	12 ea	tn	\$510	\$510		
	3/4" X 10" X 21" Beam Panel Connection Embed	100 ea	tn	\$1,700.00	\$3,791		
	3/4" X 10" X 18" Beam Panel Connection Embed	54 ea	tn	\$1,700.00	\$1,751		
	3/4" X 10" X 12" Beam Panel Connection Embed	6 ea	tn	\$1,700.00	\$119		
	5/8" X 10" X 10" Panel Embed Plates	872 ea	tn	\$1,700.00	\$16,745		
	1/2" X 6" X 14" Panel Connection Plates	218 ea	tn	\$1,700.00	\$22,542		
	1/2" X 6" X 8" Joist Pocket Embed Plates	277 ea	tn	\$1,700.00	\$1,649		
	1/4" X 4" X 4" Joist Embed Plates	277 ea	tn	\$1,700.00	\$255		
	1/2" X 4" X 12" Angle Panel Base Connections	218 ea	ea	\$10.00	\$7		
	1/2" X 4" X 4" X 8" Panel Angle Connections	106 ea	tn	\$1,700.00	\$391		
	3/4" X 7" X 24" Footing Embed Plates	218 ea	tn	\$1,700.00	\$8,721		
	3/4" X 4" Expansion Bolts Footing Wall Panels	436.0 ea	ea	\$20.00	\$8,720		
	Miscellaneous	19.60 tn	tn	\$1,700.00	\$33,320		
	Erection	216.00 tn	tn	\$800.00	\$172,800		
	CHILLER BUILDING						
	4" X 4" X 1/4" Roof Angle	226 LF	tn	\$1,700.00	\$1,275		
	3/4" X 4" Expansion Bolts Roof Angle	120.0 ea	ea	\$20.00	\$2,400		
	Miscellaneous	0.0 tn	tn	\$1,700.00	\$0		
	Erection	0.75 tn	tn	\$800.00	\$600		

SPEC REF.	DESCRIPTION DIVISION 5 - STEEL	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	COVERED PLAY BUILDING						
	4" X 4" X 1/4" Roof Angle	0.48	tn	\$1,700.00	\$816		
	3/4" X 4" Expansion Bolts Roof Angle	80.0	ea	\$20.00	\$1,600		
	Miscellaneous	1.0	tn	\$1,700.00	\$1,700		
	Erection	0.48	tn	\$800.00	\$384		
5210	STEEL JOIST					\$173,742	
	ONE STORY BUILDING						
	24 K 12 Steel Joist	3.48	tn	\$1,500.00	\$5,220		
	24 K 10 Steel Joist	21.11	tn	\$1,500.00	\$31,665		
	18 K 10 Steel Joist	5.03	tn	\$1,500.00	\$7,545		
	18 K 9 Steel Joist	4.11	tn	\$1,500.00	\$6,165		
	18 K 6 Steel Joist	6.91	tn	\$1,500.00	\$10,365		
	18 K 4 Steel Joist	1.59	tn	\$1,500.00	\$2,385		
	16 K 2 Steel Joist	0.39	tn	\$1,500.00	\$585		
	Erection	42.6	tn	\$800.00	\$34,096		
	TWO STORY BUILDING						
	18 K 10 Steel Joist	28.31	tn	\$1,500.00	\$42,465		
	18 K 4 Steel Joist	1.59	tn	\$1,500.00	\$2,385		
	12 K 1 Steel Joist	2.09	tn	\$1,500.00	\$3,135		
	Erection	32.0	tn	\$800.00	\$25,592		
	COVERED PLAY BUILDING						
	12 K 2 Steel Joist	0.29	tn	\$1,500.00	\$435		
	Erection	0.29	tn	\$800.00	\$232		
	CHILLER BUILDING						
	12 K 2 Steel Joist	0.64	tn	\$1,500.00	\$960		
	Joist Erection	0.64	tn	\$800.00	\$512		
5311	STEEL ROOF DECK					\$123,716	
	One Story Bldg. Roof Decking 1 1/2" 22Gage	38.389	sf	\$1.50	\$57,584		
	Two Story Bldg. Roof Decking 1 1/2" 22Gage	42.666	sf	\$1.50	\$63,999		
	Chiller Bldg. Roof Decking 1 1/2" 22Gage	822	sf	\$1.50	\$1,233		
	Covered Play Bldg. Roof Decking 1 1/2" 22Gage	600	sf	\$1.50	\$900		
5313	STEEL FLOOR DECK					\$59,878	
	Two Story Bldg 2nd Floor 2" Floor Decking 18 Gage	34.216	sf	\$1.75	\$59,878		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
5500	METAL FABRICATIONS					\$17,885	
	Roof Hatch	2	EA	\$600.00	\$1,200		
	Ships Ladder - 25'	1	EA	\$2,500.00	\$2,500		
	Galv Roof Access Ladder 20'	1	EA	\$1,500.00	\$1,500		
	Stair Noisings	171	LF	\$10.00	\$1,710		
	Elevator Pit Ladder and Sills	1	EA	\$500.00	\$500		
	2" X 2" Steel Frame with 2" X 2" Woven Wire Mesh Fabric	331	SF	\$25.00	\$8,275		
	Stage Curtain Supports	1	EA	\$2,200.00	\$2,200		
5510	METAL STAIRS					\$72,000	
	Metal Pan Stairs, Landings & Picket Handrail	6	FLT	\$12,000.00	\$72,000		
5520	RAILINGS					\$72,050	
	Aluminum Railings - Wall @ 3 Stairs	182	lf	\$150.00	\$27,300		
	Aluminum Railings - Standing 42" 2 Rail Picket @ 3 Stairs	84	lf	\$200.00	\$16,800		
	Aluminum Railings - Wall 2 Rail (Stage Ramp) Inside	26	lf	\$150.00	\$3,900		
	Aluminum Railings - 42" 2 Rail Picket (Stage Ramp) Inside	47	lf	\$200.00	\$9,400		
	Aluminum Railings - Wall 2 Rail (Stage Ramp) Outside	27	lf	\$150.00	\$4,050		
	Aluminum Railings - Standing 2 Rail (Stage Ramp) Outside	7	lf	\$200.00	\$1,400		
	Aluminum Railings - 42" 2 Rail Picket (Stage Ramp) Outside	46	lf	\$200.00	\$9,200		
5805	EXPANSION JOINTS					\$25,800	
	Expansion Joint Covers - Floor	250		\$30.00	\$7,500		
	Expansion Joint Covers - Wall	116		\$50.00	\$5,800		
	Expansion Joint Covers - Ceiling	250		\$50.00	\$12,500		
	TOTAL DIVISION 5 - STEEL				\$1,422,250	\$1,422,250	

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
6114	ROUGH CARPENTRY					32,205	
	Wood Blocking at Roof Exp Jt- 2x8 PT	188	lf	6.50	1,222		
	Wood Blocking at Roof Exp Jt- 2x6 PT	188	lf	6.00	1,128		
	Wood Blocking at Roof Exp Jt- 2x4 PT	210	lf	5.50	1,155		
	Wood Blocking at Roof Penetrations - 2 - 2X 6	200	lf	9.50	1,900		
	Wood Blocking Top of Parapet - 2x12 PT Bldg 1	55	lf	7.50	413		
	Wood Blocking Top of Parapet - 2x8 PT Bldg 1	1,169	lf	6.50	7,599		
	Wood Blocking Top of Parapet - 2x8 PT Bldg 2	1,549	lf	6.50	10,069		
	Wood Blocking Top of Parapet - 2x8 PT Chiller Bldg.	150	lf	6.50	975		
	Wood Blocking Top of Parapet - 2x8 PT Covered Play	114	lf	6.50	741		
	Wood Blocking Roof Hatch - 2x8 PT Bldg 1	10	lf	6.50	65		
	Wood Blocking Roof Hatch - 2x6 PT Bldg 1	20	lf	6.00	120		
	Wood Blocking Roof Hatch - 2x8 PT Bldg 2	10	lf	6.50	65		
	Wood Blocking Roof Hatch - 2x6 PT Bldg 2	20	lf	6.00	120		
	Wood Blocking at Louver - 1x6 PT	204	lf	3.50	714		
	Rough Hardware	1	ls	4,000.00	4,000		
	Plywood Panels for Electric Backboards	256	sf	7.50	1,920		
6200	FINISH CARPENTRY					2,060	
	Hardwood Block for Pencil Sharpeners	55	ea	20.00	1,100		
	Peg Board	96	sf	10.00	960		
6410	CUSTOM CASEWORK					601,335	
	Coat Pegs on Board - 4 lf/room	220	lf	25.00	5,500		
	Type I Built-in Bookcase 5'-0" X 3'-4" X 15"	235	lf	90.00	21,150		
	Type J 1 Media Cabinet 2'-0" X 5'-0" X 24" Lockable	26	lf	500.00	13,000		
	Type J 2 Media Cabinet 2'-0" X 5'-0" X 24" Lockable	22	lf	500.00	11,000		
	Type K Teacher Storage 3'-0" X 6'-0" X 18" Lockable	92	ea	650.00	59,800		
	Type L Storage Unit 3'-0" X 7'-0" X 18" Lockable	4	ea	750.00	3,000		
	Type M Storage Unit 2'-0" X 6'-0" X 18" Lockable	1	ea	500.00	500		
	Type N Storage Unit 6'-0" X 6'-0" X 18" Lockable	1	ea	1,200.00	1,200		
	Type O Computer Counter 5'-4" X 2'-6" X 30"	22	lf	60.00	1,320		
	Type P Computer Counter Varies X 2'-6" X 30"	919	lf	60.00	55,140		
	Type Q Cubbyholes 15'-3" X 3'-0" X 15"	672	lf	60.00	40,320		
	Type R Base Cabinet Varies X 2'-10" X 24" Lockable	14	lf	140.00	1,960		
	Type R Wall Cabinet Varies X 2'-6" X 12" Lockable	14	lf	110.00	1,540		
	Type S Open Base Mail Boxes Varies X 6'-2" X 24/12"	12	lf	410.00	4,920		
	Type S Base Cabinet Varies X 2'-10" X 24" Lockable	20	lf	110.00	2,200		
	Type S Wall Cabinet Varies X 2'-6" X 12" Lockable	20	lf	140.00	2,800		
	Type T Open Wall Shelving Varies X 2'-6" X 12"	17	lf	90.00	1,530		
	Type T Open Base Shelving Varies X 2'-6" X 24"	11	lf	110.00	1,210		
	Type U Open & Closed Wall Shelving Varies X 2'-6" X 18" Locks	15	lf	90.00	1,350		
	Type U Base Shelving Varies X 2'-6" X 30" Lockable	15	lf	140.00	2,100		
	Type V Open Wall Shelving Varies X 2'-6" X 12"	8	lf	90.00	720		
	Type V Countertop Base Varies X 2'-6" X 24"	7	lf	50.00	350		
	Type V Wall Cabinets Varies X 2'-6" X 12" Lockable	9	lf	110.00	990		

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	Type V Base Cabinet Varies X 2'-6" X 24" Lockable	11	If	140.00	1,540		
	Type W Wall Cabinets Varies X 2'-6" X 12" Lovkable	82	If	110.00	9,020		
	Type W Base Cabinet Varies X 2'-6" X 24" Lockable	117	If	140.00	16,380		
	Type X Wall Cabinets Varies X 2'-6" X 12" Lovkable	15	If	110.00	1,650		
	Type X Base Cabinet Varies X 2'-6" X 24" Lockable	16	If	140.00	2,240		
	Type Y Wall Cabinets Varies X 2'-6" X 12" Lovkable	15	If	110.00	1,650		
	Type Y Base Cabinet Varies X 2'-6" X 24" Lockable	16	If	140.00	2,240		
	Type Z Wall Cabinets Varies X 2'-6" X 12" Lovkable	9	If	110.00	990		
	Type Z Base Cabinet Varies X 2'-6" X 24" Lockable	10	If	140.00	1,400		
	Type AA Wall Cabinets Varies X 2'-6" X 12" Lovkable	30	If	110.00	3,300		
	Type AA Base Cabinet Varies X 2'-6" X 24" Lockable	32	If	140.00	4,480		
	Type BB Wall Cabinets Varies X 2'-6" X 12" Lovkable	30	If	110.00	3,300		
	Type BB Base Cabinet Varies X 2'-6" X 24" Lockable	32	If	140.00	4,480		
	Type CC Wall Cabinets Varies X 2'-6" X 12" Lovkable	30	If	110.00	3,300		
	Type CC Base Cabinet Varies X 2'-6" X 24" Lockable	32	If	140.00	4,480		
	Type DD Wall Cabinets Varies X 2'-6" X 12" Lovkable	15	If	110.00	1,650		
	Type DD Base Cabinet Varies X 2'-6" X 24" Lockable	16	If	140.00	2,240		
	Type EE Wall Cabinets Varies X 2'-6" X 12" Lovkable	36	If	110.00	3,960		
	Type EE Base Cabinet Varies X 2'-6" X 24" Lockable	37	If	140.00	5,180		
	Type FF Wall Cabinets Varies X 2'-6" X 12" Lovkable	14	If	110.00	1,540		
	Type FF Base Cabinet Varies X 2'-6" X 24" Lockable	15	If	140.00	2,100		
	Type GG Wall Cabinets Varies X 2'-6" X 12" Lovkable	113	If	110.00	12,430		
	Type GG Base Cabinet Varies X 2'-6" X 24" Lockable	124	If	140.00	17,360		
	Type HH Wall Cabinets Varies X 2'-6" X 12" Lovkable	128	If	110.00	14,080		
	Type HH Base Cabinet Varies X 2'-6" X 24" Lockable	138	If	140.00	19,320		
	Type II Wall Cabinets Varies X 2'-6" X 12" Lovkable	14	If	110.00	1,540		
	Type II Base Cabinet Varies X 2'-6" X 24" Lockable	15	If	140.00	2,100		
	Type JJ Wall Cabinets Varies X 2'-6" X 12" Lovkable	14	If	110.00	1,540		
	Type JJ Base Cabinet Varies X 2'-6" X 24" Lockable	15	If	140.00	2,100		
	Type KK Wall Cabinets Varies X 2'-6" X 12" Lovkable	73	If	110.00	8,030		
	Type KK Base Cabinet Varies X 2'-6" X 24" Lockable	78	If	140.00	10,920		
	Type LL Wall Cabinets Varies X 2'-6" X 12" Lovkable	73	If	110.00	8,030		
	Type LL Base Cabinet Varies X 2'-6" X 24" Lockable	78	If	140.00	10,920		
	Type MM Wall Cabinets Varies X 2'-6" X 12" Lovkable	16	If	110.00	1,760		
	Type MM Base Cabinet Varies X 2'-6" X 24" Lockable	17	If	140.00	2,380		
	Type NN Wall Cabinets Varies X 2'-6" X 12" Lovkable	13	If	110.00	1,430		
	Type NN Base Cabinet Varies X 2'-6" X 24" Lockable	14	If	140.00	1,960		
	Type OO Wall Cabinets Varies X 2'-6" X 12" Lovkable	11	If	110.00	1,210		
	Type OO Base Cabinet Varies X 2'-6" X 24" Lockable	11	If	140.00	1,540		
	Type PP Wall Cabinets Varies X 2'-6" X 12" Lovkable	16	If	110.00	1,760		
	Type PP Base Cabinet Varies X 2'-6" X 24" Lockable	17	If	140.00	2,380		
	Type QQ Wall Cabinets Varies X 2'-6" X 12" Lovkable	16	If	110.00	1,760		
	Type QQ Base Cabinet Varies X 2'-6" X 24" Lockable	17	If	140.00	2,380		

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL		REMARKS
						TOTAL	TOTAL	
	Type RR Wall Cabinets Varies X 2'-6" X 12" Lovkable	18	If	110.00	1,980			
	Type RR Base Cabinet Varies X 2'-6" X 24" Lockable	18	If	140.00	2,520			
	Type SS Wall Cabinets Varies X 2'-6" X 12" Lovkable	24	If	110.00	2,640			
	Type SS Base Cabinet Varies X 2'-6" X 24" Lockable	50	If	140.00	7,000			
	Type TT Open Wall Cabinets Varies X 2'-6" X 12"	24	If	90.00	2,160			
	Type TT Base Cabinet Varies X 2'-6" X 24" Lockable	24	If	140.00	3,360			
	Type UU Open Wall Cabinets Varies X 2'-6" X 12"	24	If	90.00	2,160			
	Type UU Open Base Cabinet Varies X 2'-6" X 24"	44	If	120.00	5,280			
	Type VV Wall Cabinets Varies X 2'-6" X 12" Lockable	30	If	110.00	3,300			
	Type VV Counter Top Varies X 2'-6" X 24"	30	If	60.00	1,800			
	Type WW Open Wall Cabinets Varies X 2'-6" X 12"	8	If	110.00	880			
	Type WW Base Cabinet Varies X 2'-6" X 24" Lockable	8	If	110.00	880			
	Type XX Open Wall Cabinets Varies X 2'-6" X 12"	19	If	90.00	1,710			
	Type XX Open Base Cabinet Varies X 2'-6" X 24"	19	If	110.00	2,090			
	Type YY Counter Top w/ End Base Varies X 2'-6" X 24" Lock	19	If	50.00	950			
	Type ZZ Wall Cabinets Varies X 2'-6" X 12" Lockable	18	If	110.00	1,980			
	Type ZZ Base Cabinet Varies X 2'-6" X 24" Lockable	18	If	140.00	2,520			
	Type AAA Glass Display Cases 6'-0" X 4'-0" X 16" Lockable	7	ea	1,080.00	7,560			
	Type BBB Adjustablr Wall Shelving 13'-0" X 4'-6" X 12"	48	If	60.00	2,880			
	Type CCC Adjustablr Wall Shelving Varies X 4'-6" X 12"	32	If	60.00	1,920			
	Type DDD Music Storage Cabinets 2'-3" X 7'-2" X 39"	35	If	225.00	7,875			
	Type EEE Instrument Storage Cabinets 4'-0" X 7'-2" X 39"	8	If	150.00	1,200			
	Media Reception Counter	26	If	300.00	7,800			
	Type FFF Reception Counter 34'-6" X 3'-6" X 30"	38	If	300.00	11,400			
	Type GGG Wall Cabinets Varies X 2'-6" X 12" Lovkable	18	If	110.00	1,980			
	Type GGG Base Cabinet Varies X 2'-6" X 24" Lockable	18	If	140.00	2,520			
	Type HHH Wall Cabinets Varies X 2'-6" X 12" Lovkable	17	If	110.00	1,870			
	Type HHH Base Cabinet Varies X 2'-6" X 24" Lockable	17	If	140.00	2,380			
	Type HHH Counter Top 14'-0" X 2'-6" X 24"	14	If	60.00	840			
	Type III Teachers Work Station / File 13'-6" X 2'-6" X 30"	850	If	60.00	51,000			
	Hanging Pegs at PE Storage	10	If	50.00	500			
	Prep for Cabinet Locks	1,250	ea	15.00	18,750			
	TOTAL DIVISION 6 - CARPENTRY				635,600		635,600	

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
7104	MEMBRANE WATERPROOFING					\$1,680	
	Elevator Pit	336	sf	\$5.00	\$1,680		
7255	CEMENTITIOUS FIREPROOFING					\$103,889	
	Fireproofing - Roof Joists One Story Building	26,233	sf	\$0.60	\$15,740		
	Fireproofing - Roof Beams One Story Building	15,812	sf	\$0.60	\$9,487		
	Fireproofing - Roof Joists Two Story Building	17,526	sf	\$0.60	\$10,516		
	Fireproofing - Roof Beams Two Story Building	4,737	sf	\$0.60	\$2,842		
	Fireproofing - 2nd Floor Beams Two Story Building	27,785	sf	\$0.60	\$16,671		
	Fireproofing - Roof Deck One Story Building	38,389	sf	\$0.60	\$23,033		
	Fireproofing - Roof Deck Two Story Building	42,666	sf	\$0.60	\$25,600		
7270	FIRESTOPPING					\$6,250	
	Firestopping at Exp. Joints 1" FB-97	125	lf	\$50.00	\$6,250		By Trades
	Firestopping at Mech & Elec Openings	0	sf	\$0.00	\$0		By Trades
	Firestop at CMU TOW (Main Building)	0	lf	\$0.00	\$0		By Trades
	Firestop at CMU TOW (Chiller / Covered Play Area)	0	lf	\$0.00	\$0		By Trades
	Firestop at Drywall TOW (See 9110)	0	lf	\$0.00	\$0		By Trades
7536	MODIFIED BITUMEN ROOFING					\$536,101	
	Roofing - One Story Building	383.9	SQ	\$650.00	\$249,529		
	Roofing - Two Story Building	426.7	SQ	\$650.00	\$277,329		
	Roofing - Chiller Building	8.2	SQ	\$650.00	\$5,343		
	Roofing - Covered Play Building	6.0	SQ	\$650.00	\$3,900		
	Rigid Roof Insulation	0	sq	\$0.00	\$0		Alternate
	Lt. Wt. Insul. Conc. System - Main	0	sf	\$0.00	\$0		Incl In Roofing
	Lt. Wt. Insul. Conc. System - Mech. & Play	0	sf	\$0.00	\$0		Incl In Roofing
	Tapered Insulation at Crickets	0	sf	\$0.00	\$0		Alternate
	Exp. Jt.	0	lf	\$0.00	\$0		Incl In Roofing
7610	S.S. METAL ROOFING					\$0	
	At Roof between Buildings	0	sf	\$0.00	\$0		see Walkway Covers
	At Shed Roofs at Exterior Corridors	0	sf	\$0.00	\$0		see Walkway Covers
7620	SHEET METAL FLASHING AND TRIM					\$81,925	
	8" Cap Flashing/Coping One Story Building	1,169	lf	\$15.00	\$17,535		
	8" Cap Flashing/Coping Two Story Building	1,549	lf	\$15.00	\$23,235		
	8" Cap Flashing/Coping Covered Play Building	115	lf	\$15.00	\$1,725		
	8" Cap Flashing/Coping Chiller Building	150	lf	\$15.00	\$2,250		
	Counter Flashings at Parapet	2,916	lf	\$8.00	\$23,328		
	Surface Reglets @ Parapets	2,916	lf	\$3.00	\$8,748		
	Counter Flashing w/ High/Low Roof	255	lf	\$8.00	\$2,040		
	Reglets @ High/Low Roof	383	lf	\$8.00	\$3,064		
	Downspout Boots	0	ea	\$0.00	\$0		

SPEC REF.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
7631	DIVISION 7 - THERMAL & MOISTURE PROTECTION GUTTERS AND DOWNSPOUTS					\$30,300	
	Scuppers	29	ea	\$150.00	\$4,350		
	Overflow Scuppers	58	ea	\$75.00	\$4,350		
	6" Gutters	0	lf	\$0.00	\$0		
	8" Downspouts	540	lf	\$40.00	\$21,600		
7724	ROOF HATCHES					\$1,200	
	Roof Hatches	2	ea	\$600.00	\$1,200		
7900	JOINT SEALERS					\$46,973	
	Exterior H. M. Frames (Outside Face Of Frame)	942	lf	\$1.25	\$1,178		
	Exterior H. M. Frames (Inside Face Of Frame)	942	lf	\$1.25	\$1,178		
	Exterior Windows (Outside Face Of Frame)	2,924	lf	\$1.25	\$3,655		
	Exterior Windows (Inside Face Of Frame)	2,924	lf	\$1.25	\$3,655		
	Louvers (Inside Face Of Frame)	96	lf	\$1.25	\$120		
	Louvers (Inside Face Of Frame)	96	lf	\$1.25	\$120		
	Interior Windows	3,296	lf	\$0.25	\$824		
	Interior H. M. Frames	5,000	lf	\$0.25	\$1,250		
	Masonry Walls	150	lf	\$1.25	\$188		
	Scuppers	87	ea	\$25.00	\$2,175		
	Tilt-Wall Panels One Story Building Exterior 2 Sides	3,078	lf	\$2.50	\$7,695		
	Tilt-Wall Panels Two Story Building Exterior 2 Sides	4,940	lf	\$2.50	\$12,350		
	Tilt-Wall Panels Two Story Building Interior 2 Sides	1,710	lf	\$2.50	\$4,275		
	Tilt-Wall Panels Fire Rated Elevator 2 Sides	264	lf	\$5.00	\$1,320		
	Tilt-Wall Panels Fire Rated 2 Sides	1,050	lf	\$5.00	\$5,300		
	Interior SOG Joints at Exposed Concrete	1,353	lf	\$1.25	\$1,691		
		0					
	TOTAL DIVISION 7 -				\$808,317	\$808,317	

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
8111	STEEL DOORS					\$63,955	
	H.M. Doors @ One Story Admin. Building 3'-0" X 7'-0"	17	ea	\$250.00	\$4,250		
	H.M. Doors @ One Story Media Building 3'-0" X 7'-0"	2	ea	\$250.00	\$500		
	H.M. Doors @ One Story Media Building 3'-4" X 7'-0"	1	ea	\$280.00	\$280		
	H.M. Doors @ One Story Dining Building 3'-0" X 7'-0"	5	ea	\$245.00	\$1,225		
	H.M. Doors @ One Story Dining Building 3'-4" X 7'-0"	2	ea	\$280.00	\$560		
	H.M. Doors @ One Story Kitchen Building 3'-0" X 7'-0"	23	ea	\$245.00	\$5,635		
	H.M. Doors @ One Story Kitchen Building 3'-4" X 7'-0"	4	ea	\$280.00	\$1,120		
	H.M. Doors @ One Story Kitchen Building 4'-0" X 7'-0"	1	ea	\$350.00	\$350		
	H.M. Doors @ Site Single Kynar With SS Wire Mesh 4'-0" X 7'-0"	2	ea	\$800.00	\$1,600		
	H.M. Doors @ Site Double Kynar With SS Wire Mesh 4'-0" X 7'-0"	8	ea	\$800.00	\$6,400		
	S/S Screens At Site Doors	320	sf	\$50.00	\$16,000		
	H.M. Doors 1st Floor 3'-10" X 7'-0"	2	ea	\$350.00	\$700		
	H.M. Doors 1st Floor 3'-0" X 7'-0"	33	ea	\$245.00	\$8,085		
	H.M. Doors 2nd Floor 3'-0" X 7'-0"	16	ea	\$245.00	\$3,920		
	H.M. Doors 2nd Floor 3'-7" X 7'-0"	1	ea	\$280.00	\$280		
	H.M. Doors Covered Play Building 3'-0" X 7'-0"	5	ea	\$245.00	\$1,225		
	H.M. Doors @ Chiller Building 3'-0" X 7'-0"	5	ea	\$245.00	\$1,225		
	H.M. Doors @ Chiller Building 3'-4" X 7'-0"	3	ea	\$280.00	\$840		
	H.M. Doors @ Chiller 4'-0" X 7'-0"	2	ea	\$350.00	\$700		
	Exterior Window Lite Kits	7	ea	\$50.00	\$350		
	Labor to Unload HM Door Leaves 1 st Floor	105	ea	\$10.00	\$1,050		
	Labor to Unload HM Door Leaves 2 nd Floor	17	ea	\$20.00	\$340		
	Labor to Install HM Door Leaves	122	ea	\$60.00	\$7,320		
8112	STEEL FRAMES					\$68,350	
	H.M. Door Frames Typr F-1 3'-4" X 7'-4"	6	ea	\$105.00	\$630		
	H.M. Door Frames Typr F-1 3'-8" X 7'-4"	1	ea	\$105.00	\$105		
	H.M. Door Frames Typr F-1 6'-4" X 7'-4"	2	ea	\$105.00	\$210		
	H.M. Door Frames Typr F-1 7'-0" X 7'-4"	1	ea	\$105.00	\$105		
	H.M. Door Frames Type F-1 8'-4" X 7'-4"	1	ea	\$105.00	\$105		
	H.M. Door Frames Type F-1 3'-4" X 7'-2"	222	ea	\$90.00	\$19,980		
	H.M. Door Frames Type F-1 3'-8" X 7'-2"	10	ea	\$90.00	\$900		
	H.M. Door Frames Type F-1 3'-11" X 7'-2"	1	ea	\$105.00	\$105		
	H.M. Door Frames Type F-1 4'-1" X 7'-2"	2	ea	\$105.00	\$210		
	H.M. Door Frames Type F-1 4'-4 X 7'-2"	4	ea	\$105.00	\$420		
	H.M. Door Frames Type F-1 5'-4 X 7'-2"	4	ea	\$130.00	\$520		
	H.M. Door Frames Type F-1 5'-8 X 7'-2"	1	ea	\$130.00	\$130		
	H.M. Door Frames Type F-1 6'-4 X 7'-2"	35	ea	\$130.00	\$4,550		
	H.M. Door Frames Type F-1 8'-1 X 7'-2"	1	ea	\$130.00	\$130		

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	DIVISION 8 - DOORS & WINDOWS						
	H.M. Dooe Frames Type F-1 7'-0" X 7'-2"	1	ea	\$130.00	\$130		
	H.M. Dooe Frames Type F-2 8'-4" X 7'-2"	8	ea	\$200.00	\$1,600		
	H.M. Dooe Frames Type F-3 8'-4" X 7'-2"	2	ea	\$200.00	\$400		
	H.M. Dooe Frames Type Site Single Kynar 3'-4" X 7'-4"	2	ea	\$200.00	\$400		
	H.M. Dooe Frames Type Site Double Kynar 8'-4" X 7'-4"	4	ea	\$300.00	\$1,200		
	H.M. Dooe Frames Type F-4 6'-4" X 7'-2" w/ 3'-4" X 3'-4" Side Lites	4	ea	\$175.00	\$700		
	H.M. Dooe Frames Type F-5 6'-4" X 8'-0" Transom	1	ea	\$140.00	\$140		
	H.M. Dooe Frames Type F-5 6'-4" X 10'-8" Transom	2	ea	\$140.00	\$280		
	H.M. Louver Frames Type 5'-4" X 4'-4"	3	ea	\$90.00	\$270		
	H.M. Louver Frames Type L-1 6'-4" X 3'-4"	1	ea	\$90.00	\$90		
	H.M. Louver Frames Type L-2 5'-4" X 3'-4"	2	ea	\$90.00	\$180		
	H.M. Louver Frames Type L-3 5'-4" X 3'-10"	1	ea	\$90.00	\$90		
	H.M. Louver Frames Type L-4 3'-10" X 2'-10"	1	ea	\$90.00	\$90		
	H.M. Window Frames Type AA 5'-0" X 5'-0"	2	ea	\$90.00	\$180		
	H.M. Window Frames Type BB 3'-0" X 5'-0"	2	ea	\$90.00	\$180		
	H.M. Window Frames Type CC 2'-8" X 4'-0"	3	ea	\$90.00	\$270		
	H.M. Window Frames Type DD 1'-8" X 2'-8"	1	ea	\$90.00	\$90		
	H.M. Window Frames Type EE 5'-0" X 7'-11"	1	ea	\$90.00	\$90		
	H.M. Window Frames Type FF 5'-0" X 4'-0"	1	ea	\$90.00	\$90		
	H.M. Window Frames Type GG 4'-6" X 6'-8"	2	ea	\$90.00	\$180		
	Labor to Unload HM Frames	336	ea	\$10.00	\$3,360		
	Labor to Install HM Door Frames	311	ea	\$90.00	\$27,990		
	Labor to Install HM Louver Frames	5	ea	\$90.00	\$450		
	Labor to Install HM Window Frames	20	ea	\$90.00	\$1,800		
						\$78,060	
8211	FLUSH WOOD DOORS						
	Fire Rated Doors: 30 Min 2'-6" X 7'-0"	6	ea	\$245.00	\$1,470		
	Fire Rated Doors: 30 Min 2'-8" X 7'-0"	2	ea	\$245.00	\$490		
	Fire Rated Doors: 30 Min 3'-0" X 7'-0"	200	ea	\$245.00	\$49,000		
	Fire Rated Doors: 30 Min 3'-7" X 7'-0"	2	ea	\$245.00	\$490		
	Fire Rated Doors: 30 Min 3'-10" X 7'-0"	2	ea	\$245.00	\$490		
	Fire Rated Doors: 30 Min 4'-0" X 7'-0"	2	ea	\$245.00	\$490		
	Fire Rated Doors: 40 Min 2'-6" X 7'-0"	2	ea	\$280.00	\$560		
	Fire Rated Doors: 40 Min 3'-0" X 7'-0"	4	ea	\$280.00	\$1,120		
	Fire Rated Doors: 40 Min 3'-4" X 7'-0"	2	ea	\$280.00	\$560		
	Interior Window Lite Kits	157	ea	\$50.00	\$7,850		
	Labor to Unload Wood Doors	222	ea	\$10.00	\$2,220		
	Labor to Install Wood Doors	222	ea	\$60.00	\$13,320		
8305	ACCESS DOORS					\$8,000	
	Access Doors	40	ea	\$200.00	\$8,000		

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
8360	OVERHEAD DOOR					\$5,000	
	OH Door Multi-Purpose Stage 14'-0" X 12'-0"	1	ea	\$3,500.00	\$3,500		
	OH Door Dish Wash 4'-0" X 14'-0"	1	ea	\$1,500.00	\$1,500		
8520	ALUMINUM WINDOWS AND DOORS					\$431,535	
	Aluminum Windows Type-A 6'-8" x 6'-0" Projected (115 ea.)	3,910	sf	\$100.00	\$391,000		
	Aluminum Windows Type-C 7'-2" x 9'-0" (1 ea.)	65	sf	\$65.00	\$4,225		
	Aluminum Windows Type-D 10'-2" x 5'-1" (2 ea.)	104	sf	\$65.00	\$6,760		
	Aluminum Windows Type-F 6'-4" x 9'-0" (0 ea.)	0	sf	\$65.00	\$0		
	Aluminum Windows Type-G 8'-0" x 5'-0" Projected (1 ea.)	40	sf	\$100.00	\$4,000		
	Aluminum Windows Type-K 6'-8" x 2'-6" (1 ea.)	15	sf	\$65.00	\$975		
	Aluminum Windows Type-M 3'-4" x 3'-0" (5 ea.)	50	sf	\$65.00	\$3,250		
	Aluminum Windows Type-M 3'-4" x 5'-0" (5 ea.)	85	sf	\$65.00	\$5,525		
	Window Screens	3,950	sf	\$4.00	\$15,800		
8710	DOOR HARDWARE					\$314,200	
	Furnish Door Hardware Type 1A	3	ea	\$505.00	\$1,515		
	Furnish Door Hardware Type 1B	27	ea	\$505.00	\$13,635		
	Furnish Door Hardware Type 1C	19	ea	\$505.00	\$9,595		
	Furnish Door Hardware Type 1D	1	ea	\$505.00	\$505		
	Furnish Door Hardware Type 1E	2	ea	\$505.00	\$1,010		
	Furnish Door Hardware Type 1F	3	ea	\$505.00	\$1,515		
	Furnish Door Hardware Type 1G	1	ea	\$505.00	\$505		
	Furnish Door Hardware Type 3A	9	ea	\$505.00	\$4,545		
	Furnish Door Hardware Type 3C	0	ea	\$505.00	\$0		
	Furnish Door Hardware Type 5	8	ea	\$505.00	\$4,040		
	Furnish Door Hardware Type 5A	46	ea	\$505.00	\$23,230		
	Furnish Door Hardware Type 5B	1	ea	\$505.00	\$505		
	Furnish Door Hardware Type 5C	28	ea	\$505.00	\$14,140		
	Furnish Door Hardware Type 5E	1	ea	\$505.00	\$505		
	Furnish Door Hardware Type 5G	6	ea	\$505.00	\$3,030		
	Furnish Door Hardware Type 5H	3	ea	\$520.00	\$1,560		
	Furnish Door Hardware Type 5J	1	ea	\$520.00	\$520		
	Furnish Door Hardware Type 5K	2	ea	\$520.00	\$1,040		
	Furnish Door Hardware Type 5L	2	ea	\$520.00	\$1,040		
	Furnish Door Hardware Type 5M	29	ea	\$520.00	\$15,080		
	Furnish Door Hardware Type 5N	2	ea	\$520.00	\$1,040		
	Furnish Door Hardware Type 5P	8	ea	\$520.00	\$4,160		
	Furnish Door Hardware Type 5Q	3	ea	\$520.00	\$1,560		
	Furnish Door Hardware Type 5R	2	ea	\$520.00	\$1,040		
	Furnish Door Hardware Type 5S	2	ea	\$520.00	\$1,040		
	Furnish Door Hardware Type 6	4	ea	\$505.00	\$2,020		
		1	ea	\$540.00	\$540		

SPEC REF	DESCRIPTION	DIVISION 8 - DOORS & WINDOWS				SECTION TOTAL	REMARKS
		QUANTITY	UNIT	UNIT COST	TOTAL		
	Furnish Door Hardware Type 6A	1	ea	\$540.00	\$540		
	Furnish Door Hardware Type 6B	2	ea	\$540.00	\$1,080		
	Furnish Door Hardware Type 7	2	ea	\$525.00	\$1,050		
	Furnish Door Hardware Type 7A	4	ea	\$5,050.00	\$20,200		
	Furnish Door Hardware Type 7B	1	ea	\$5,050.00	\$5,050		
	Furnish Door Hardware Type 7C	2	ea	\$530.00	\$1,060		
	Furnish Door Hardware Type 7D	1	ea	\$530.00	\$530		
	Furnish Door Hardware Type 7E	1	ea	\$500.00	\$500		
	Furnish Door Hardware Type 7F	1	ea	\$505.00	\$505		
	Furnish Door Hardware Type 7G	3	ea	\$525.00	\$1,575		
	Furnish Door Hardware Type 8	4	ea	\$640.00	\$2,560		
	Furnish Door Hardware Type 8A	2	ea	\$525.00	\$1,050		
	Furnish Door Hardware Type 8B	2	ea	\$540.00	\$1,080		
	Furnish Door Hardware Type 8C	2	ea	\$540.00	\$1,080		
	Furnish Door Hardware Type 8D	1	ea	\$525.00	\$525		
	Furnish Door Hardware Type 10	5	ea	\$540.00	\$2,700		
	Furnish Door Hardware Type 10A	3	ea	\$540.00	\$1,620		
	Furnish Door Hardware Type 10B	2	ea	\$540.00	\$1,080		
	Furnish Door Hardware Type 11	2	ea	\$540.00	\$1,080		
	Furnish Door Hardware Type 11A	1	ea	\$540.00	\$540		
	Furnish Door Hardware Type 12	1	ea	\$540.00	\$540		
	Furnish Door Hardware Type 12A	11	ea	\$540.00	\$5,940		
	Furnish Door Hardware Type 12B	1	ea	\$565.00	\$565		
	Furnish Door Hardware Type 12C	3	ea	\$540.00	\$1,620		
	Furnish Door Hardware Type 12D	1	ea	\$565.00	\$565		
	Furnish Door Hardware Type 12E	4	ea	\$665.00	\$2,260		
	Furnish Door Hardware Type 13	6	ea	\$565.00	\$3,390		
	Furnish Door Hardware Type 13A	2	ea	\$525.00	\$1,050		
	Furnish Door Hardware Type 14	1	ea	\$525.00	\$525		
	Furnish Door Hardware Type 14A	2	ea	\$665.00	\$1,130		
	Furnish Door Hardware Type 15	10	ea	\$565.00	\$5,650		
	Furnish Door Hardware Site Single Door	2	ea	\$2,200.00	\$4,400		
	Furnish Door Hardware Site Double Doors	8	ea	\$2,200.00	\$17,600		
	Electronic Hardware/Card Reader Premium	21	loc	\$1,000.00	\$21,000		
	Electronic Hardware/Card Reader Premium Site Doors	6	loc	\$1,000.00	\$6,000		
	Unload/Store Hardware	299	ls	\$5.00	\$1,495		
	Install Hardware	299	sets	\$100.00	\$29,900		
	Cabinet Locks - Schlage	1,250	ea	\$45.00	\$56,250		

SPEC REF	DESCRIPTION DIVISION 8 - DOORS & WINDOWS	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
8800	GLAZING					\$13,200	
	Interior Door Lites	164	ea	\$15.00	\$2,460		
	AG 1/4" Bronze Tinted Tempered (NR)	0	sf	\$20.00	\$0		
	Interior H. M. Windows	192	sf	\$25.00	\$4,800		
	Control Booth Glazing	32	sf	\$15.00	\$480		
	1/4" Clear Wired Glass	120	sf	\$25.00	\$3,000		
	Full Length Mirrors at Tchr Plan & Staff Lkrs	5	ea	\$300.00	\$1,500		
	Mirrors at Dressing Room	64	sf	\$15.00	\$960		
	TOTAL DIVISION 8 - WINDOWS & DOORS				\$982,300	\$982,300	

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
9110	METAL STUD FRAMING SYSTEM & DRYWALL					\$1,545,815	
	Type A-4 Wall 2- 5/8 GWB, 4" @ 16 oc	1,808	sf	\$5.65	\$10,215		
	Type A-4S Wall 2- 5/8 GWB, 4" @ 16 oc 4" Batt insul.	9,016	sf	\$6.25	\$56,350		
	Type A-6 Wall 2- 5/8 GWB, 6" @ 16 oc	0	sf	\$0.00	\$0		
	Type A-6 Wall 2- 5/8 GWB, 6" @ 16 oc Kitchen 56" high	61	sf	\$7.50	\$458		
	Type A-6S Wall 2- 5/8 GWB, 6" @ 16 oc 4" Batt insul.	0	sf	\$0.00	\$0		
	Type A-4 S Wall 2- 5/8 GWB, 4" @ 12 oc 4" Batt insul.	27,449	sf	\$6.85	\$188,026		
	Type A-4 XS Wall 2- 5/8 GWB, 4" @ 12 oc 4" Batt insul. Smoke	11,388	sf	\$7.85	\$89,396		
	Type A-4 XS Wall 2- 5/8 GWB, 4" @ 16 oc 4" Batt insul. Smoke	23,256	sf	\$6.85	\$159,304		
	Type A-4 X1S Wall 2- 5/8 GWB, 4" @ 16 oc 4" Batt insul. Smoke	8,982	sf	\$9.00	\$79,938		
	Type A-6 XS Wall 2- 5/8 GWB, 6" @ 16 oc 4" Batt insul. Smoke	560	sf	\$8.50	\$4,760		
	Type B-4 Wall 1- 5/8 GWB, 1-5/8 CMTB 4" @ 16 oc	552	sf	\$6.65	\$3,671		
	Type B-4S Wall 1- 5/8 GWB, 1-5/8 CMTB 4" @ 16 oc Batt. Insul	10,896	sf	\$7.25	\$78,996		
	Type B-4S Wall 1- 5/8 GWB, 1 5/8 CMTB 4" @ 16 oc 4" Batt insul.	7,797	sf	\$6.65	\$51,850		
	Type B-4 XS Wall 1- 5/8 GWB, 1 5/8 CMTB 4" @ 16 oc 4" Batt insul. Smoke	994	sf	\$7.85	\$7,803		
	Type B-6 Wall 1- 5/8 GWB, 1-5/8 CMTB 4" @ 16 oc	0	sf	\$0.00	\$0		
	Type B-6S Wall 1- 5/8 GWB, 1 5/8 CMTB 4" @ 16 oc 4" Batt insul.	1,002	sf	\$7.30	\$7,315		
	Type B-6 XS Wall 1- 5/8 GWB, 1 5/8 CMTB 4" @ 16 oc 4" Batt insul. Smoke	1,681	sf	\$9.50	\$15,970		
	Type B-6 X1S Wall 1- 5/8 GWB, 1 5/8 CMTB 4" @ 16 oc 4" Batt insul. Smoke	851	sf	\$7.15	\$6,085		
	Type C-4 Wall 2- 5/8 CMTB 4" @ 16 oc	672	sf	\$7.15	\$4,805		
	Type C-4S Wall 2- 5/8 CMTB, 4" @ 16 oc 4" Batt insul.	3,420	sf	\$7.75	\$26,505		
	Type C-6S Wall 2- 5/8 CMTB, 6" @ 16 oc 4" Batt insul.	612	sf	\$9.75	\$5,967		
	Type D-4 Wall 1- 5/8 GWB, 4" @ 16 oc 4" Batt insul.	1,848	sf	\$5.25	\$9,702		
	Type D-6 Wall 1- 5/8 GWB, 6" @ 16 oc 4" Batt insul.	0	sf	\$0.00	\$0		
	Type E Wall 2- 5/8 CMTB, 4" @ 16 oc 4" Batt insul.	184	sf	\$9.75	\$1,794		
	Type ES Wall 2- 5/8 CMTB, 4" @ 16 oc 4" Batt insul.	874	sf	\$9.75	\$8,522		
	Type FS Wall 1- 5/8 GWB, 3/4" Fur @ 16 oc	2,464	sf	\$4.25	\$10,472		
	Type FXS Wall 1- 5/8 GWB, 1 1/2" @ 16 oc w/ 1" rigid insul	5,969	sf	\$5.25	\$31,337		
	Type FX1S Wall 1- 5/8 GWB, 1 1/2" @ 16 oc w/ 1" rigid insul 1hr	58,454	sf	\$5.50	\$321,497		
	Type GS Wall 1- 5/8 GWB, 3/4" Fur @ 16 oc	3,703	sf	\$4.25	\$15,738		
	Type GX Wall 1- 5/8 GWB, 1 1/2" @ 16 oc w/ 1" rigid insul	0	sf	\$0.00	\$0		
	Type HS Wall 1- 5/8 GWB, 3/4" Fur @ 16 oc	5,206	sf	\$4.25	\$22,126		
	Type HXS Wall 1- 5/8 GWB, 1 1/2" @ 16 oc w/ 1" rigid insul	7,570	sf	\$5.25	\$39,743		
	Type HX1S Wall 1- 5/8 GWB, 1 1/2" @ 16 oc w/ 1" rigid insul 1hr	989	sf	\$5.50	\$5,440		
	Type JX1 Shaft Wall 3- 5/8 Type GWB 1 Side 3 5/8" @ 16 oc w/ 4" batt 1 hr	616	sf	\$10.00	\$6,160		
	Type LX1S Shaft Wall 3- 5/8 Type GWB 1 Side 3 5/8" @ 16 oc w/ 4" batt 1 hr	168	sf	\$10.00	\$1,680		
	Type MS Wall 2- 5/8 GWB, 4" @ 16 oc 4" Smoke.	0	sf	\$0.00	\$0		
	Type MXS Wall 2- 5/8 GWB, 4" @ 16 oc 4" Batt insul. Smoke	1,920	sf	\$6.85	\$13,152		

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	DIVISION 9 - FINISHES						
	Wrap Steel Columns 1 hr Two Story 1st Floor	664	lf	\$45.00	\$29,880		
	Wrap Steel Columns 1 hr Two Story 2nd Floor	690	lf	\$45.00	\$31,050		
	Wrap Steel Columns 1 hr One Story	529	lf	\$45.00	\$23,805		
	Ceiling Soffits and Drops Covered Play	123	sf	\$10.00	\$1,230		
	Ceiling Soffits and Drops Two Story 2nd	3,388	sf	\$10.00	\$33,880		
	Ceiling Soffits and Drops Two Story 1st	3,710	sf	\$10.00	\$37,100		
	Ceiling Soffits and Drops One Story	4,413	sf	\$10.00	\$44,130		
	Abuse resist. GWB to 8' at Corrid, Multipurp. - Extra Cost	33,597	sf	\$0.75	\$25,198		
	Bathroom Ceilings - 3-1/2" Framing w/ 5/8" GWB	6,011	sf	\$5.00	\$30,055		
	Metal Framing at Stucco Soffits	943	sf	\$5.00	\$4,715		
	Metal Framing & Sheathing at Play Building Clg. & Gables	0	sf	\$0.00	\$0		
9220	PORTLAND CEMENT PLASTER					\$41,830	
	Stucco Soffits	175	syd	\$50.00	\$8,750		
	Stucco On Masonry - Play Area Building	190	syd	\$40.00	\$7,600		
	Stucco On Masonry at Dumpster	32	syd	\$40.00	\$1,280		
	Stucco On Masonry - Chiller Building/Yard Ext. Wall	605	syd	\$40.00	\$24,200		
9215	VEENER PLASTER					\$42,000	
	Multipurpose (14')	5,502.00	sf	\$1.25	\$6,878		
	One Story Corridors (9')	5,508.00	sf	\$1.25	\$6,885		
	Two Story 1st Corridors (9')	10,980.00	sf	\$1.25	\$13,725		
	Two Story 2nd Corridors (9')	11,610.00	sf	\$1.25	\$14,513		
9306	CERAMIC/QUARRY FLOOR TILE					\$95,628	
	Bathrooms	4,274	SF	\$7.00	\$29,918		
	Ceramic Wall Cove Base	2,183	LF	\$6.50	\$14,190		
	Marble Saddles/Thresholds	222	LF	\$6.00	\$1,332		
	Quarry Tile Floors	3,404	SF	\$8.00	\$27,232		
	Quarry Tile Base	503	LF	\$7.50	\$3,773		
	Epoxy Grout for Quarry Tile	3,404	SF	\$3.50	\$11,914		
	Marble Window Sills	727	LF	\$10.00	\$7,270		
9307	WALL TILES					\$148,257	
	Ceramic Wall Tile - Kitchen	4,821	SF	\$6.75	\$32,542		
	Ceramic Wall Tile - Single Bathrooms	16,423	SF	\$6.75	\$110,855		
	Ceramic Wall Tile - Gang Bathrooms	720	SF	\$6.75	\$4,860		
9440	ACOUSTICAL WALL PANELS					\$51,636	
	Acoustical Wall Panels - Music	48	SF	\$12.00	\$576		
	Acoustical Wall Panels - Multi-Purpose	3,270	SF	\$14.00	\$45,780		
	Acoustical Wall Panels - Media	320	SF	\$12.00	\$3,840		
	Acoustical Wall Panels - CCTV	120	SF	\$12.00	\$1,440		

SPEC REF	DESCRIPTION DIVISION 9 - FINISHES	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
9511	ACOUSTICAL CEILINGS					\$134,267	
	2'X4' Acoustical Ceiling Panels & Grid @ Covered Play	110	SF	\$1.50	\$165		
	2'X4' Plastic Coated Surface Ceiling Tiles @ Kiln	90	SF	\$2.50	\$225		
	2'X4' Acoustical Ceiling Panels & Grid Two Story 1st	28,654	SF	\$1.50	\$42,981		
	2'X4' Acoustical Ceiling Panels & Grid Two Story 2nd	29,176	SF	\$1.50	\$43,764		
	2'X4' Acoustical Ceiling Panels & Grid One Story Admin.	9,659	SF	\$1.50	\$14,489		
	2'X4' Acoustical Ceiling Panels & Grid One Story Media	6,191	SF	\$1.50	\$9,287		
	2'X4' Acoustical Ceiling Panels & Grid One Story Stage	1,124	SF	\$1.50	\$1,686		
	2'X4' Acoustical Ceiling Panels & Grid One Story Kitchen/Receiving	3,796	SF	\$1.50	\$5,694		
	2'X2' Acoustical Ceiling Panels & Grid One Story Media	2,536	SF	\$1.60	\$4,058		
	2'X2' Acoustical Ceiling Panels & Grid One Story Dining	4,551	SF	\$1.60	\$7,282		
	2'X4' Plastic Coated Surface Ceiling Tiles @ Kitchen	1,855	SF	\$2.50	\$4,638		
9650	RESILIENT FLOOR					\$166,807	
	VCT One Story Building	28,251	SF	\$1.40	\$39,551		
	VCT Two Story Building 1st	31,597	SF	\$1.40	\$44,236		
	VCT Two Story Building 2nd	32,861	SF	\$1.40	\$46,005		
	Non-Slip VCT @ Stage Ramp	150	SF	\$1.75	\$263		
	Vinyl Base	18,264	LF	\$1.25	\$22,830		
	Sheet Flooring @ Clinic	456	SF	\$4.50	\$2,052		
	Sheet Vinyl Base @ Clinic	148	LF	\$5.00	\$740		
	Resilient Stair Nosings(Stage)	126	LF	\$17.50	\$2,205		
	Resilient Stair Nosings, Treads, Risers - (15'-4") 17" x 3 ea	510	LF	\$17.50	\$8,925		
9688	CARPET					\$1,020	
	Carpet 2 Principal Office	34	SYD	\$30.00	\$1,020		
9900	PAINTING					\$222,927	
	Interior Gyp Walls	162,650	sf	\$0.44	\$71,566		
	Interior CMU Walls	22,840	sf	\$0.66	\$15,074		
	Exterior Tilt-up Walls	105,563	sf	\$0.83	\$87,617		
	Chiller Building Stucco	5,445	sf	\$0.60	\$3,267		
	Dumpster Stucco	288	sf	\$0.70	\$202		
	Play Building Stucco	1,710	sf	\$0.65	\$1,112		
	Stucco Soffits	1,575	sf	\$0.70	\$1,103		
	Exterior Door Frames	47	ea	\$65.00	\$3,055		
	Interior Door Frames	289	ea	\$45.00	\$13,005		
	Interior Window Frames	14	ea	\$55.00	\$770		
	Exterior Doors	47	ea	\$65.00	\$3,055		
	Interior Doors	75	ea	\$0.00	\$0		
	Epoxy Painting at Corridors & Multi-purpose to 9'	0	sf	\$0.65	\$0		
	Covered Play Area METAL BLDG	3,000	sf	\$1.10	\$3,300		

SPEC REF	DESCRIPTION DIVISION 9 - FINISHES	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	Drywall Ceilings	11,634	sf	\$0.55	\$6,399		
	Stairs	3	ea	\$1,500.00	\$4,500		
	Conc. Floors	5,328	sf	\$0.80	\$4,262		
	Paint Exposed Structure One Story	2,980	sf	\$0.70	\$2,086		
	Paint Exposed Structure Two Story	3,650	sf	\$0.70	\$2,555		
	Bollards	0	ea	\$25.00	\$0		
	TOTAL DIVISION 9 - FINISHES				\$2,450,187	\$2,450,187	

SPEC REF	DESCRIPTION DIVISION 10 - SPECIALTIES	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
10105	VISUAL DISPLAY BOARDS					\$71,240	
	Marker Boards - 16' x 4'	48	EA	\$720.00	\$34,560		
	Marker Boards - 8' x 4' w/ Music Staff Lines	0	EA	\$480.00	\$0		
	Marker Boards - 8' x 4'	10	EA	\$360.00	\$3,600		
	Marker Boards - 6' x 4'	0	EA	\$270.00	\$0		
	Map Rail & Accessories	900	LF	\$3.00	\$2,700		
	Flag Holders	48	EA	\$10.00	\$480		
	Tack Boards - 8' x 4'	62	EA	\$240.00	\$14,880		
	Tack Boards - 6' x 4'	4	EA	\$180.00	\$720		
	Tack Boards - 4' x 4'	100	EA	\$120.00	\$12,000		
	Tack Boards - 3' x 4'	5	EA	\$100.00	\$500		
	Tack Wall Surface - Art Room	240	SF	\$7.50	\$1,800	\$5,900	
10171	TOILET PARTITIONS						
	Standard Stall	3	EA	\$1,000.00	\$3,000		
	Handicap Stall	2	EA	\$1,250.00	\$2,500		
	Urinal Screens	1	EA	\$400.00	\$400		
10191	CUBICLE CURTAINS & TRACK					\$1,800	
	Cubical Curtain & Track at Clinic	30	lf	\$60.00	\$1,800		
10211	FIXED METAL WALL LOUVERS					\$10,040	
	Type L1 Louver - 6' x 3'	2	ea	\$540.00	\$1,080		
	Type L2 Louver - 5' x 3'	3	ea	\$450.00	\$1,350		
	Type L3 Louver - 5' x 2'-6"	2	ea	\$375.00	\$750		
	Type L4 Louver - 3'-6" x 2'-6"	2	ea	\$300.00	\$600		
	Type L5 Louver - 2' x 2'	2	ea	\$200.00	\$400		
	Type L6 Louver - 1' x 1'	4	ea	\$75.00	\$300		
	Type L7 Louver - 6' x 1'-6"	2	ea	\$270.00	\$540		
	Type L8 Louver - 6' x 3'-6"	3	ea	\$650.00	\$1,950		
	Type L9 Louver - 6' x 4'-6"	2	ea	\$800.00	\$1,600		
	Type L10 Louver - 3'-6" x 7'	2	ea	\$735.00	\$1,470		
10260	CORNER GUARDS					\$10,125	
	Corridor Corner Guards	135	EA	\$75.00	\$10,125		
10350	FLAGPOLES					\$5,600	
	Flagpole Assembly	2	ea	\$1,600.00	\$3,200		
	Installation	2	ls	\$1,200.00	\$2,400		
10400	IDENTIFYING DEVICES					\$53,430	
	Room Capacity [Over 50 Persons- Dining & Library]	2	ea	\$50.00	\$100		
	Interior Signs	288	ea	\$40.00	\$11,440		
	Door Signs	307	ea	\$30.00	\$9,210		
	Fish Signs	288	ea	\$10.00	\$2,880		
	Emrg(4), FE(54), Pull sta(14), Occ., Stair(6), Stor(56).	134	ea	\$40.00	\$5,360		
	Toilet Signs	60	ea	\$40.00	\$2,400		
	HC(1), Elev(2), Freezer(1), Cooler(1), Visitor(2), Roof Signs(0)	7	ea	\$40.00	\$280		
	Exit Routes	60	ea	\$50.00	\$3,000		

SPEC REF	DESCRIPTION DIVISION 10 - SPECIALTIES	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
	Exterior Signs	28	ea	\$60.00	\$1,680		
	Building Identification Letters	11	Loc	\$500.00	\$5,500		
	Plaque	1	ea	\$1,600.00	\$1,600		
	14" Channel Letters	0	ea	\$150.00	\$0		None Shown
	Marquee Sign	1	ea	\$10,000.00	\$10,000		
10508	LOCKERS					\$5,250	
	Food Service Lockers - 12x12x72 - 1 Tier	15	ea	\$250.00	\$3,750		
	Custodial Service Lockers - 12x12x72 - 1 Tier	6	ea	\$250.00	\$1,500		
10522	FIRE EXTINGUISHERS, CABINETS, ACCESS.					\$9,340	
	Fire Extinguisher Cabinets	38	ea	\$160.00	\$6,080		
	Fire Extinguisher Brackets	20	ea	\$20.00	\$400		
	Fire Extinguishers	54	ea	\$40.00	\$2,160		
	Fire Extinguishers Type K	4	ea	\$75.00	\$300		
	Fire Blankets	2	ea	\$200.00	\$400		
10532	ALUMINUM WALKWAY COVERS					\$240,020	
	Tower Element at Parent Drop	2,000	sf	\$22.00	\$44,000		
	Tower Element at Center Court	0	sf	\$0.00	\$0		
	Flat Walkway at Building	4,500	sf	\$19.00	\$85,500		
	Flat Walkway at Building - radius	0	SF	\$0.00	\$0		
	Flat Walkway Cover at Bus Drop-Off	0	SF	\$0.00	\$0		
	Flat Walkway Cover at Bus Drop-Off Radius	1,500	sf	\$21.00	\$31,500		
	Art Area Canopy	400	sf	\$30.00	\$12,000		
	Building to Building Flat Walkway Cover	0	SF	\$0.00	\$0		
	Kind. Play Canopy	500	sf	\$30.00	\$15,000		
	48" Eyebrows @ Doors	207	lf	\$60.00	\$12,420		
	12" Eyebrows @ Windows	880	lf	\$45.00	\$39,600		
10605	WIRE MESH PARTITIONS					\$0	
	Wire Partition 10' High @ Receiving	0	lf	\$0.00	\$0		
10600	FOLDING PANEL PARTITIONS					\$0	
	Partitions - Multipurpose	0	sf	\$0.00	\$0		none shown
	Partitions - Other	0	sf	\$0.00	\$0		none shown
10670	STORAGE SHELVING					\$68,420	
	Central Receiving (18'd x 72'h x 36'w)	40	ea	\$300.00	\$12,000		
	Equipment Storage (18'd x 72'h x 36'w)	28	ea	\$300.00	\$8,400		
	CCTV/AV Storage (18'd x 72'h x 36'w)	46	ea	\$300.00	\$13,800		
	Kindergarten Storage (18'd x 72'h x 36'w)	0	ea	\$300.00	\$0		
	ESE Department Storage (18'd x 72'h x 36'w)	14	ea	\$300.00	\$4,200		
	Custodial - Service Closets (12'd x 48" x 36" w)	15	ea	\$180.00	\$2,700		
	Golf Cart - Storage (12'd x 48" x 36" w)	5	ea	\$180.00	\$900		
	Stage Storage (12'd x 72" h x 36" w)	11	ea	\$240.00	\$2,640		
	PE Storage (36" d x 72" h x 36" w)	6	ea	\$480.00	\$2,880		
	Textbook Storage (18'd x 72" h x 36" w)	36	ea	\$300.00	\$10,800		
	Admin. Storage Area	90	ea	\$100.00	\$9,000		
	Primary Storage	11	ea	\$100.00	\$1,100		

SPEC REF	DESCRIPTION DIVISION 10 - SPECIALTIES	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
10800	TOILET & BATH ACCESSORIES					\$50,010	
	Paper Towel Dispenser at Casework	58	ea	\$44.00	\$2,552		
	Soap Dispenser at Casework	58	ea	\$99.00	\$5,742		
	Paper Towel Dispenser/Disposal Combo	64	ea	\$88.00	\$5,632		
	Toilet Tissue Dispenser: Single Roll	66	ea	\$22.00	\$1,452		
	Sanitary Napkin Dispenser	18	ea	\$200.00	\$3,600		
	Grab Bar: 42"	60	ea	\$55.00	\$3,300		
	Grab Bar: 36"	60	ea	\$44.00	\$2,640		
	Grab Bar: Continuous	4	ea	\$160.00	\$640		
	Sanitary Napkin Disposal	0	ea	\$44.00	\$0		
	Soap Dispenser - Wall Mount	68	ea	\$99.00	\$6,732		
	Mop/Broom Holder	0	ea	\$0.00	\$0		
	Mirror; Handicap, Tilting 18" x 30"	68	ea	\$110.00	\$7,480		
	Mirror; Fixed 18" x 24"	0	ea	\$66.00	\$0		
	S.S. Shelf	0	ea	\$66.00	\$0		
	Shower Curtain & Rod	4	ea	\$140.00	\$560		
	Shower Seat	4	ea	\$165.00	\$660		
	Fold Down Changing Table	2	ea	\$400.00	\$800		
	First Aid Cabinet [Ed. Spec.]	2	ea	\$110.00	\$220		
	Installation	1	ls	\$8,000.00	\$8,000		
	TOTAL DIVISION 10 - SPECIALTIES				\$531,175	\$531,175	

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
11020	SPECIALTY ITEMS					28,200	
	Flammable Storage Cabinet	1	ea	500.00	500		
	TV/CR Ceiling Brackets	60	ea	350.00	21,000		
	TV/CR Wall Brackets	0	ea	0.00	0		
	Knox Box	2	ea	350.00	700		
	Safe	1	ea	2,500.00	2,500		
	Supervision Mirror	1	ea	750.00	750		
	Book Drop Return	1	ea	2,000.00	2,000		
	Lockable Narcotics Cab. 24"x10"x30"	1	ea	750.00	750		
11062	STAGE CURTAINS					15,800	
	Stage Curtains and Track	330	sf	20.00	6,600		
	CCTV Curtain & Track	560	sf	7.50	4,200		
	CCTV Pipe Grid	500	sf	10.00	5,000		
11110	PROJECTION SCREENS					19,200	
	Projection Screen: Electric (72" x96")	2	EA	900.00	1,800		
	Projection Screen: Manual (72" x 96")	58	EA	300.00	17,400		
11400	FOOD SERVICE EQUIPMENT					375,000	
	Food Service Equipment	1	LS	375,000	375,000		
11450	RESIDENTIAL EQUIPMENT					13,450	
	Washer/Dryer - Heavy Duty - Kitchen Laundry	1	EA	1,200.00	1,200		
	Washer/Dryer - Commercial/Dryer - Central Receiving	1	EA	3,600.00	3,600		
	Refrigerator	7	EA	950.00	6,650		
	u/Counter Refrigerator	1	ea	400.00	400		
	Microwave	4	EA	400.00	1,600		
11480	ATHLETIC/PLAYGROUND EQUIPMENT					0	see sitework
	Backstops, Sleeves, play surfacing, Striping	0		0.00	0		
	Playcourt Striping	0	ls	0.00	0		
	Basketball Backboards	0	EA	1,800.00	0		
	Sleeves w/covers for Volleyball Standards	0	EA	500.00	0		
	TOTAL DIVISION 11 - EQUIPMENT				451,650	451,650	

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
12345	LABORATORY CASEWORK					3,500	
	Kiln @ Art Room	1	ls	3,500.00	3,500		
12380	DISPLAY CASE					0	
	Display at Reception	0	ea	0.00	0		W/Casework Div. 6
	Display at Media	0	ea	0.00	0		W/Casework Div. 6
	Display at Art	0	ea	0.00	0		W/Casework Div. 6
12500	WINDOW TREATMENTS					15,192	
	Vertical Blinds at Windows	4,269	sf	3.50	14,942		
	Interior Horizontal Blinds	100	sf	2.50	250		
12692	FLOOR MATS					11,000	
	Surface Mat at Double Doors	10	ea	900.00	9,000		
	Surface Mat at Single Doors	4	ea	500.00	2,000		
12800	MISCELLANEOUS FURNISHINGS					1,144	
	Pencil Sharpeners	52	ea	22.00	1,144		
	Battery Clocks	0	ea		0		w/electrical division
	GPS Transmitter/Repeater	0	ea		0		w/electrical division
	TOTAL DIVISION 12 - FURNISHINGS				30,836	30,836	

C.R. Klewin Southeast, Inc.

PALM BEACH GARDENS ELEMENTARY SCHOOL
G. M. P. ESTIMATE

Estimate Date 3-28-07
Printed 3/28/2007 3:46 PM

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
13120	PRE - ENGINEERED BUILDING					99,000	
	Play Area Shelter - 50' x 62'	3,000	sf	33.00	99,000		
TOTAL DIVISION 13 SPECIAL CONSTRUCTION						99,000	99,000

C.R. Klewin Southeast, Inc.

PALM BEACH GARDENS ELEMENTARY SCHOOL
G. M. P. ESTIMATE

Estimate Date 3-28-07
Printed 3/28/2007 3:46 PM

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
14245	DIVISION 14 - CONVEYING SYSTEMS					46,500	
	HYDRAULIC ELEVATOR						
	Hydraulic Passenger Elevator - 2 Stop 2100# Capacity	1	Ea	46,500	46,500		
	TOTAL DIVISION 14 - CONVEYING SYSTEMS				46,500	46,500	

SPEC REF	DESCRIPTION	DIVISION: 15 - MECHANICAL SYSTEMS				SECTION TOTAL	REMARKS
		QUANTITY	UNIT	UNIT COST	TOTAL		
15400	PLUMBING				\$816,600		
	Building 1 - Kitchen, Multi-Purp., Media	0	sf	\$0.00	Incl.		
	Building 2 - Classroom	0	sf	\$0.00	Incl.		
	Building 8 - Classroom	0	sf	\$0.00	Incl.		
	Building 6 - Covered Play Area	0	sf	\$0.00	Incl.		
	Total						
	Sanitary	0	lf	\$0.00	Incl.		
	Domestic Water	0	lf	\$0.00	Incl.		
	Fixtures & Accessories & Roughing						
	P1 - Water Closet, Fl. Mtd.	51	ea	\$0.00	Incl.		
	P2 - Water Closet, Fl. Mtd., ADA	15	ea	\$0.00	Incl.		
	P3 - Water Closet, Wl. Mtd., ADA	2	ea	\$0.00	Incl.		
	P4 - Water Closet, Wl. Mtd.	3	ea	\$0.00	Incl.		
	P5 - Urinal	1	ea	\$0.00	Incl.		
	P5A - Urinal, ADA	1	ea	\$0.00	Incl.		
	P6 - Lav., ADA	70	ea	\$0.00	Incl.		
	P7 - Lav., ADA, H. & C. Water	2	ea	\$0.00	Incl.		
	P8 - Sink, Clinic, H. & C. Water	1	ea	\$0.00	Incl.		
	P9 - Sink, Cl. Rm.	40	ea	\$0.00	Incl.		
	P10 - Sink, Counter	1	ea	\$0.00	Incl.		
	P11 - Sink, Counter, ADA	1	ea	\$0.00	Incl.		
	P12 - Double Sink, Cl. Rm., ADA	1	ea	\$0.00	Incl.		
	P13 - Double Sink, Cl. Rm.	7	ea	\$0.00	Incl.		
	P14 - Sink, Counter	1	ea	\$0.00	Incl.		
	P15 - Dual Elec. Water Cooler	5	ea	\$0.00	Incl.		
	P16 - Mop Sink	4	ea	\$0.00	Incl.		
	P17 - Shower, ADA, Hot & Cold Water	4	ea	\$0.00	Incl.		
	P18 - Laundry Tub	1	ea	\$0.00	Incl.		
	P19 - Washing Machine Tub	1	ea	\$0.00	Incl.		
	P20 - Laundry Tub	1	ea	\$0.00	Incl.		
	P21 - Combo. Emerg. Shower/Eye Wash	1	ea	\$0.00	Incl.		
	P22 - Cond. Box	1	ea	\$0.00	Incl.		
	Can Wash	1	ea	\$0.00	Incl.		
	Hose Bib	10	ea	\$0.00	Incl.		
	Floor Drain	10	ea	\$0.00	Incl.		
	Total Fixt., Access. & Roughing - Avg. Pricing	236	ea	\$3,100.00	\$731,600		
	Water Heaters/Pumps (4)	1	sum	\$30,000.00	\$30,000		
	Insulation	0	lf	\$0.00	\$0		
	Install Fixtures - F.B.O.	0	ea	\$0.00	\$0		
	Kitchen Hook-ups	1	ls	\$25,000.00	\$25,000		
	Gas Piping - Kitchen	1	ls	\$15,000.00	\$15,000		

SPEC REF	DESCRIPTION	DIVISION 15 - MECHANICAL SYSTEMS				SECTION TOTAL	REMARKS
		QUANTITY	UNIT	UNIT COST	TOTAL		
	Sewer Tank	0	ea	\$0.00	\$0		
	Water Tank	0	ea	\$0.00	\$0		
	Grease Tanks	1	ea	\$10,000.00	\$10,000		
	Site Drinking Fountains	2	ea	\$2,500.00	\$5,000		
15495	FIRE PROTECTION					\$288,100	
	Fire Protection System						
	Building - Kitchen, Multi-Purp., Media	30,000	sf	\$2.50	\$75,000		
	Building - Classroom	83,000	sf	\$2.50	\$207,500		
	Building - Play Area	700	sf	\$3.50	\$2,450		
	Chiller Mech. Space	900	sf	\$3.50	\$3,150		
15600	H.V.A.C.					\$2,260,400	
	Building - Kitchen, Multi-Purp., Media	30,000	sf	\$22.00	\$660,000		
	Building - Classroom	83,000	sf	\$19.00	\$1,577,000		
	Building - Play Area	700	sf	\$18.00	\$12,600		
	Chiller Mech. Space	900	sf	\$12.00	\$10,800		
	Total HVAC System	114,600	sf		\$0		
	Air Handling Units		ls	\$0.00	Incl		
	Water Chillers		ls	\$0.00	Incl		
	Duct Insulation		ls	\$0.00	Incl		
	HVAC - Water Pumps		ls	\$0.00	Incl		
	Chilled Water Piping		ls	\$0.00	Incl		
	Chilled Water Piping Insulation		ls	\$0.00	Incl		
	Variable Frequency Drives		ls	\$0.00	Incl		
	Hydronic Specialties		ls	\$0.00	Incl		
	Temperature Control Wiring		ls	\$0.00	Incl		
	Duct Heaters		ls	\$0.00	Incl		
	Grill/Registers/Diffusers		ls	\$0.00	Incl		
	VAV Boxes		ls	\$0.00	Incl		
	Fans / Louvers / Vents		ls	\$0.00	Incl		
	Mechanical Identification		ls	\$0.00	Incl		
	Fire Dampers		ls	\$0.00	Incl		
	Smoke Dampers		ls	\$0.00	Incl		
	Testing		ls	\$0.00	Incl		
	Start-up		ls	\$0.00	Incl		
	Excavation & Backfill		ls	\$0.00	Incl		
	VFDs are provided by the Owner's Control Vendor						
	Testing & Balancing are provided by Thae Owner						
	TOTAL DIVISION 15 - MECHANICAL SYSTEMS				\$3,365,100		

SPEC REF	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL	SECTION TOTAL	REMARKS
16000	ELECTRICAL					2,723,700	
	Building 1 - Kitchen, Multi-Purp., Media	30,000	sf	25.00	750,000		
	Building - Classroom	83,000	sf	22.00	1,826,000		
	Building - Chiller Mech. Space	900	sf	18.00	16,200		
	Building - Play Area - Enclosed	700	sf	18.00	12,600		
	Building - Play Area - Under Cover	3,000	sf	6.00	18,000		
	Total	117,600	sf				
	Lighting at Covered Walkways	9,000	sf	4.00	36,000		
	Life Safety Upgrades at Existing Buildings		sf	2.00	0		
	Temporary Power		ls	0.00	0		
	Power Distribution Equipment		ls	0.00	0		
	Motor & Equipment Connections		ls	0.00	0		
	Power Feed Raceways		ls	0.00	0		
	Power Feed Wire		ls	0.00	0		
	Branch Power & Lighting Raceways		ls	0.00	0		
	Branch Power & Lighting Wire		ls	0.00	0		
	Wiring Devices		ls	0.00	0		
	Lighting Fixtures		ls	0.00	0		
	Fire Alarm		ls	0.00	0		
	Fire Alarm Equip.		ls	0.00	0		
	Fire Alarm Rcwys.		ls	0.00	0		
	Fire Alarm Wire		ls	0.00	0		
	Sound/Intercom		ls	0.00	0		
	Sound/Intercom Equip.		ls	0.00	0		
	Sound/Intercom Rcwys.		ls	0.00	0		
	Sound/Intercom Wire		ls	0.00	0		
	T. V. System (SIRSI / Proj / Rad / Reg)		ls	0.00	0		
	T. V. Antenna Tower		ls	0.00	0		
	Telephone Raceway		ls	0.00	0		
	Telephone Wire		ls	0.00	0		
	Security System Raceway		ls	0.00	0		
	Tele Data Rcwys		ls	0.00	0		
	Energy System Raceway		ls	0.00	0		
	GPS Master Satellite Clock System - New	114,000	sf	0.35	39,900		
	GPS Master Satellite Clock System - Existing		sf	0.00	0		
	Audio Enhancement System						Excluded
	Projectors Incl. Ceiling Mount						Excluded
	Grounding		ls	0.00	0		
	Generator		ls	0.00	0		
	Site Lighting		ls	0.00	0		
	Site Electrical & Communications		ls	0.00	0		
	ITV Tower	1	ls	25,000	25,000		
	TOTAL DIVISION 16 ELECTRICAL SYSTEMS				2,723,700	2,723,700	

PRE-CONSTRUCTION

Act ID	Activity Description	Orig Dur	Early Start	Early Finish	Total Float	%
1000	Pre-Construction	177d	05OCT05	08JUN06	-1d	0
1010	Select C.R. Klewin as CM	1d	05OCT05	05OCT05	-1d	0
1020	Schematic Design, Estimate, Review	13d	04JAN06	20JAN06	-1d	0
1040	Design Dev./50% Estimate, Review	16d	08AUG06	29AUG06	-1d	0
1030	100% Construction Documents to Permit	16d	05JAN07	26JAN07	-1d	0
1050	GMP Estimate	25d	01FEB07	07MAR07	-1d	0
1060	SFWM Permit Issued	1d	01FEB07	01FEB07	89d	0
1070	Submit GMP for Board Approval	1d	18APR07	18APR07	-1d	0

- Pre-Construction
- Select C.R. Klewin as CM
- Schematic Design, Estimate, Review
- Design Dev./50%, Estimate, Review
- 100% Construction Documents to Permit
- GMP Estimate
- SFWM Permit Issued
- Submit GMP for Board Approval

DEMOLITION

1090	Demolition	17d	01JUN07	25JUN07	-1d	0
1100	Notify Health Dept of Demolition	6d	01JUN07	08JUN07	-1d	0
1110	Asbestos Abatement	5d	11JUN07	15JUN07	-1d	0
1120	Terminate Utilities	5d	18JUN07	22JUN07	-1d	0
1130	Remove Bulbs and Ballasts	5d	18JUN07	22JUN07	-1d	0
1140	Demolition of Structures	9d	18JUN07	28JUN07	-1d	0

- Demolition
- Notify Health Dept of Demolition
- Asbestos Abatement
- Terminate Utilities
- Remove Bulbs and Ballasts
- Demolition of Structures

CONSTRUCTION

1160	Construction	284d	29JUN07	08AUG08	-1d	0
1170	Notice to Proceed	1d	29JUN07	29JUN07	-1d	0
1180	New Construction	264d	29JUN07	11JUL08	-1d	0
1190	Site Construction	264d	29JUN07	11JUL08	-1d	0
1200	Existing Building Work	66d	29JUN07	02OCT07	-1d	0
1210	Concrete	74d	29JUN07	12OCT07	0	0
1220	Electrical	283d	29JUN07	07AUG08	-1d	0
1230	Mechanical	236d	16JUL07	17JUN08	-1d	0
1240	Masonry	32d	25SEP07	08NOV07	-1d	0
1250	Steel	27d	15OCT07	21NOV07	-1d	0
1260	Carpentry	31d	09NOV07	26DEC07	-1d	0
1270	Thermal and Moisture Protection	27d	24DEC07	01FEB08	-1d	0
1280	Windows and Doors	29d	08JAN08	18FEB08	-1d	0
1290	Elevator	37d	04FEB08	26MAR08	55d	0
1300	Specialties	40d	27MAR08	22MAY08	55d	0
1320	Finishes	73d	02APR08	16JUL08	-1d	0
1310	Equipment	24d	07APR08	09MAY08	64d	0

- Construction
- Notice to Proceed
- New Construction
- Site Construction
- Existing Building Work
- Concrete
- Electrical
- Mechanical
- Masonry
- Steel
- Carpentry
- Thermal and Moisture Protection
- Windows and Doors
- Elevator
- Specialties
- Finishes
- Equipment

Start date	05OCT05
Finish date	12AUG08
Data date	05OCT05
Run date	21FEB07
Page number	1A

Early bar
 Progress bar
 Critical bar
 Summary bar
 Progress point
 Critical point
 Summary point
 Start milestone point
 Finish milestone point

C.R.Klewin SE, Inc
Palm Beach Gardens Elementary School

Act ID	Activity Description	Orig Dur	Early Start	Early Finish	Total Float	%
1330	Substantial Completion	0	11JUL08	11JUL08	-1d	0
1340	Move Into New Facility	21d	14JUL08	12AUG08	-1d	0
1350	Final Completion	0	12AUG08	12AUG08	-1d	0

2006 | 2007 | 2008 | 2009 | 2010 | 2011 | 2012 | 2013 | 2014 | 2015 | 2016 | 2017 | 2018 | 2019 | 2020 | 2021 | 2022 | 2023 | 2024 | 2025 | 2026 | 2027 | 2028

▲ Substantial Completion
 ▲ Move Into New Facility
 ▲ Final Completion

Start date: 05OCT05
 Finish date: 12AUG08
 Data date: 05OCT05
 Run date: 21FEB07
 Page number: 2A

C.R.Klewin SE, Inc
Palm Beach Gardens Elementary School

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFls
01 - Cover Page								
A0.00	0	COVER AND INDEX SHEET	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A0.00AS11	4	COVER AND INDEX SHEET	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A0.01	0	GENERAL NOTES	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
02 - Survey								
SURVEY	0	SURVEY	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
03 - Civil								
C-1.0	0	GENERAL NOTES	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
C-10.1	0	WATER & SEWER DETAILS (1 OF 3)	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
C-10.2	0	WATER & SEWER DETAILS (2 OF 3)	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
C-10.3	3	WATER & SEWER DETAILS (3 OF 3)	1/17/2007	2/6/2007	100	Construction Documents	10/25/06	
C-2.1	2	CIVIL SITE AND GEOMETRY PLAN (1 OF 2)	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
C-2.2	2	CIVIL SITE AND GEOMETRY PLAN (2 OF 2)	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
C-3.0	2	GRADING	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
C-4.0	3	PAVEMENT AND GROUND COVER PLAN	1/17/2007	2/6/2007	100	Construction Documents	10/25/06	
C-5.0	3	TYPICAL SECTIONS	1/17/2007	2/6/2007	100	Construction Documents	10/25/06	
C-6.0	2	DRAINAGE PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
C-7.0	3	SIGNING AND PAVEMENT PLAN	1/17/2007	2/6/2007	100	Construction Documents	10/25/06	
C-8.0	3	PAVING GRADING AND DRAINAGE DETAILS	1/17/2007	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref REIs
C-9.0	3	WATER & SANITARY SEWER PLAN	1/17/2007	2/6/2007	100	Construction Documents	10/25/06	
CSD-01	2	SURFACE DEMOLITION PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
04 - Landscape								
L1.0	2	PLANTING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
L1.1	2	PLANTING DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
L2.0	2	IRRIGATION PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
L2.1	2	IRRIGATION PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
L2.2	2	IRRIGATION PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
L2.3	2	IRRIGATION PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
L2.4	2	IRRIGATION NOTES AND DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
05 - Architectural								
A1.00	1	OVERALL SITE PLAN	10/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.00AS11	2	OVERALL SITE PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A1.01	2	PARTIAL SITE PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.02	2	PARTIAL SITE PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.03	2	PARTIAL SITE PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.04	2	PARTIAL SITE PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.04AS11	3	PARTIAL SITE PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A1.05	1	SITE SIGNAGE AND	10/25/2006	2/6/2007	100	Construction	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
PARKING DETAILS								
A1.06	0	SITE DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.07	0	PARKING AND SIDEWALK DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.08	0	COVERED WALKWAY DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.09	1	PLAY COURT AND FIELD DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A1.10	2	PLAY FIELD DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.01	0	OVERALL GROUND FLOOR PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.01A	2	PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.01AAS11	3	PARTIAL GROUND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.01AS11	3	OVERALL GROUND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.01B	2	PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.01BAS11	3	PARTIAL GROUND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.01C	2	PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.01CAS11	3	PARTIAL GROUND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.01D	2	PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.01DAS11	3	PARTIAL GROUND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.01E	2	PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.01EAS11	3	PARTIAL GROUND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.01F	0	PARTIAL GROUND FLOOR PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
A2.01FASH1	3	PARTIAL GROUND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.02	0	OVERALL SECOND FLOOR PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.02A	2	PARTIAL SECOND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.02AAS11	3	PARTIAL SECOND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.02AS11	3	OVERALL SECOND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.02B	2	PARTIAL SECOND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.02BAS11	3	PARTIAL SECOND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.02C	2	PARTIAL SECOND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.02CAS11	3	PARTIAL SECOND FLOOR PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.03	1	ROOF PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A2.03AS11	2	ROOF PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A2.04	2	ROOF DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.01	0	OVERALL GROUND FLOOR REFLECTED CEILING PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.01A	2	PARTIAL GROUND FLOOR REFLECTED CEILING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.01AS11	3	OVERALL GROUND FLOOR REFLECTED CEILING PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A3.01B	2	PARTIAL GROUND FLOOR REFLECTED CEILING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.01C	2	PARTIAL GROUND FLOOR REFLECTED CEILING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.01D	2	PARTIAL GROUND FLOOR REFLECTED CEILING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

Prolog Manager

Printed on: 3/28/2007

CRKSE

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
A3.01E	2	PARTIAL GROUND FLOOR REFLECTED CEILING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.01F	0	PARTIAL GROUND FLOOR-REFLECTED CEILING PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.02	0	OVERALL SECOND FLOOR REFLECTED CEILING PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.02A	2	PARTIAL SECOND FLOOR REFLECTED CEILING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.02B	2	PARTIAL SECOND FLOOR REFLECTED CEILING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.02C	2	PARTIAL SECOND FLOOR REFLECTED CEILING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A3.03	0	CEILING DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.01	0	EXTERIOR ELEVATIONS (SOUTH)	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.01AS11	1	EXTERIOR ELEVATIONS (SOUTH)	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A4.02	0	EXTERIOR ELEVATIONS (WEST)	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.02AS11	1	EXTERIOR ELEVATIONS (WEST)	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A4.03	0	EXTERIOR ELEVATIONS (NORTH & EAST)	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.03AS11	1	EXTERIOR ELEVATIONS (NORTH & EAST)	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A4.04	0	EXTERIOR ELEVATIONS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.04AS11	1	EXTERIOR ELEVATIONS	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A4.10	2	BUILDING SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.11	2	BUILDING SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.20	2	WALL SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
A4.20	AS11	3 WALL SECTIONS	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A4.21		2 WALL SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.21	AS11	3 WALL SECTIONS	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A4.22		2 WALL SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A4.22	AS11	3 WALL SECTIONS	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A4.30		2 JOINT DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A5.01		2 ENLARGED STAIR PLANS & SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A5.01	AS11	3 ENLARGED STAIR PLANS & SECTIONS	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A5.02		2 RAMP AND ELEVATOR PLANS & SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A5.20		0 ENLARGED TOILET PLANS, 1ST FLOOR & ELEVATIONS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A5.21		0 ENLARGED TOILET PLANS, 1ST FLOOR & ELEVATIONS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A5.25		0 RESTROOM MOUNTING HEIGHTS & ACCESSORIES	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A6.01		2 TYPICAL PARTITION TYPES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A6.01	AS11	2 TYPICAL PARTITION TYPES	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A6.02		2 WALL AND PLAN DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A6.03		2 WALL AND PLAN DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A7.01		2 DOOR & WINDOW TYPES AND SCHEDULE	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A7.01	AS11	3 DOOR & WINDOW TYPES AND SCHEDULE	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	

Prolog Manager

Printed on: 3/28/2007

CRKSE

Page 6

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
A7.02	2	DOOR, WINDOW LOUVER TYPES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A7.02AS11	3	DOOR, WINDOW LOUVER TYPES	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A7.03	2	DOORS WINDOWS DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A7.03AS11	3	DOORS WINDOWS DETAILS	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A8.00	2	CASEWORK ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A8.00AS11	3	CASEWORK ELEVATIONS	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A8.01	2	CASEWORK ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.01	2	FINISH SCHEDULE	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.01A	0	PARTIAL GROUND FLOOR - FINISH PLAN & SIGNAGE	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.01AS11	3	FINISH SCHEDULE	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
A9.01B	0	PARTIAL GROUND FLOOR - FINISH PLAN & SIGNAGE	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.01C	0	PARTIAL GROUND FLOOR - FINISH PLAN & SIGNAGE	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.01D	0	PARTIAL GROUND FLOOR - FINISH PLAN & SIGNAGE	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.01E	2	PARTIAL GROUND FLOOR - FINISH PLAN & SIGNAGE	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.01F	2	PARTIAL GROUND FLOOR - FINISH PLAN & SIGNAGE	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.02A	0	PARTIAL 2ND FLOOR - FINISH PLAN & SIGNAGE	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.02B	0	LIFE SAFETY PAR. 2ND FLOOR - FINISH PLAN & SIGN.	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.02C	0	PARTIAL 2ND FLOOR - FINISH PLAN & SIGN.	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	

Prolog Manager

Printed on: 3/28/2007

CRKSE

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
A9.11	0	OVERALL GROUND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.11A	0	PARTIAL GROUND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.11B	0	PARTIAL GROUND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.11C	0	PARTIAL GROUND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.11D	0	PARTIAL GROUND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.11E	0	PARTIAL GROUND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.11F	0	PARTIAL GROUND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.12	0	OVERALL 2ND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.12A	0	PARTIAL 2ND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.12B	0	PARTIAL 2ND FLOOR - 7/26/2006 FLOOR PATTERN PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
A9.30	0	SIGNAGE LEGEND	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
DA.00	2	OVERALL SITE DEMOLITION PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
DA.00ASI1	3	OVERALL SITE DEMOLITION PLAN	2/28/2007	3/9/2007	100	Construction Documents	02/28/07	
LS.00	1	LIFE SAFETY GENERAL NOTES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.01	1	LIFE SAFETY - OVERALL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.01A	1	LIFE SAFETY - PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.01B	1	LIFE SAFETY - PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.01C	1	LIFE SAFETY - PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

Prolog Manager

Printed on: 3/28/2007

CRKSE

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
LS.01D	1	LIFE SAFETY - PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.01E	1	LIFE SAFETY - PARTIAL GROUND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.01F	0	LIFE SAFETY - PARTIAL GROUND FLOOR PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.02	1	LIFE SAFETY - OVERALL SECOND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.02A	1	LIFE SAFETY - PARTIAL SECOND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.02B	1	LIFE SAFETY - PARTIAL SECOND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.02C	1	LIFE SAFETY - PARTIAL SECOND FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.1	0	LIFE SAFETY FIRE RESISTIVITY UL DESIGNS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.2	0	LIFE SAFETY FIRE RESISTIVITY UL DESIGNS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.3	0	LIFE SAFETY FIRE RESISTIVITY UL DESIGNS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.4	0	LIFE SAFETY FIRE RESISTIVITY UL DESIGNS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
LS.5	1	LIFE SAFETY CONCEPTUAL OVERALL EVAC PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
07 - Structural								
S-0.0	2	STRUCTURAL NOTES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-1.1	2	FOUNDATION AND FIRST FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-1.2	2	FOUNDATION AND FIRST FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-1.3	2	FOUNDATION AND FIRST FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-1.4	2	FOUNDATION AND FIRST FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-1.5	2	FOUNDATION AND FIRST FLOOR PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
S-2.1	2	FLOOR PLAN SECOND FLOOR FRAMING PLAN	10/25/2006	2/6/2007	100	Documents	10/25/06	
S-2.2	2	SECOND FLOOR FRAMING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-2.3	2	SECOND FLOOR FRAMING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-3.1	2	ROOF FRAMING PLAN	10/25/2006	2/6/2007	10	Construction Documents	10/25/06	
S-3.2	2	ROOF FRAMING PLAN	10/25/2006	2/6/2007	10	Construction Documents	10/25/06	
S-3.3	2	ROOF FRAMING PLAN	10/25/2006	2/6/2007	10	Construction Documents	10/25/06	
S-3.4	2	ROOF FRAMING PLAN	10/25/2006	2/6/2007	10	Construction Documents	10/25/06	
S-3.5	2	ROOF FRAMING PLAN	10/25/2006	2/6/2007	10	Construction Documents	10/25/06	
S-4.1	2	SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-4.2	2	SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-4.3	2	SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-4.4	2	SECTIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-5.1	2	TILT-UP PANELS REINFORCEMENT ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-5.2	2	TILT-UP REINFORCEMENT ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-5.3	2	TILT-UP ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-5.4	2	TILT-UP REINFORCEMENT ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-5.5	2	TILT-UP PANELS REINFORCEMENT ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev.Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
S-5.6	2	TILT-UP REINFORCEMENT ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-5.7	2	TILT-UP REINFORCEMENT ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-5.8	2	TILT-UP PANELS REINFORCEMENT ELEVATIONS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-6.1	2	DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-6.2	2	DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-6.3	2	DETAILS AND SCHEDULES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
S-7.1	2	SCHEDULES AND DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
08 - Mechanical								
M0.01	1	LEGEND, SCHEDULES & GENERAL NOTES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M0.02	0	MECHANICAL SCHEDULES	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M0.03	0	MECHANICAL SCHEDULES	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M0.04	0	MECHANICAL SCHEDULES	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M1.01	1	BLDG.2 - PARTIAL 1ST FLOOR HVAC PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M1.02	1	BLDG.2 - PARTIAL 2ND FLOOR HVAC PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M1.03	1	BLDG.2 - PARTIAL 1ST & 2ND FLOOR HVAC PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M1.04	1	BUILDING 1 & 4 - HVAC PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M1.05	1	BUILDING 3 HVAC PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M2.01	0	BLDG.2 - MECHANICAL ROOM PLAN - FIRST FLOOR	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFI's
M2.02	1	BLDG.2 - MECHANICAL ROOM PLAN - SECOND FLOOR	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M2.03	0	BLDG.2 - MECHANICAL ROOM PLAN - FIRST FLOOR	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M2.04	1	BLDG.2 - MECHANICAL ROOM PLAN - SECOND FLOOR	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M2.05	0	BLDG.1 - MECHANICAL ROOM PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M2.06	0	BLDG.3 - MECHANICAL ROOM PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M2.07	1	BLDG.3 - MECHANICAL ROOM PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M2.08	0	LARGE SCALE CHILLER YARD PLAN & SCHEMATIC	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M2.09	0	MECHANICAL SITE PIPING PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M3.01	0	MECHANICAL DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M3.02	0	MECHANICAL DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M3.03	1	MECHANICAL DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
M3.04	0	MECHANICAL DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M4.01	0	MECHANICAL CONTROLS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
M4.02	0	MECHANICAL CONTROLS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
09 - Plumbing								
P0.01	1	SCHEDULES, LEGEND & GENERAL NOTES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P0.02	1	PLUMBING DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P1.01	1	PLUMBING FLOOR PLAN - PARTIAL BLDG. 2	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

Prolog Manager

Printed on: 3/28/2007

CRKSE

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFIs
UNDERGROUND PIPING								
P1.02	1	PLUMBING FLOOR PLAN - PARTIAL BLDG. 2	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P1.03	1	PLUMBING FLOOR PLAN - BLDG. 1,4 & 5	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P1.04	1	PLUMBING FLOOR PLAN - BLDG. 3 UNDERGROUND PIPING	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P1.05	1	PLUMBING FLOOR PLAN - BLDG. 2 UNDERGROUND PIPING PARTIAL	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P1.06	1	PLUMBING FLOOR PLAN - BLDG 1 & 4	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P1.07	1	PLUMBING FLOOR PLAN - BLDG 3 UNDERGROUND PIPING	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P2.01	1	PLUMBING FLOOR PLAN - PARTIAL BLDG. 2, 2ND FLOOR	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P2.02	1	PLUMBING FLOOR PLAN - PARTIAL BLDG. 2, 2ND FLOOR	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P3.01	1	ENLARGED KITCHEN PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P4.01	1	RISER DIAGRAMS PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P4.02	1	DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
P4.03	1	PLUMBING ROOF PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
10 - Electrical								
E0.01	1	ELECTRICAL SITE PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E0.02	1	ELECTRICAL SITE PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.01	1	BLDG. 2 PARTIAL LIGHTING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFI's
E1.02	1	BUILDING 2 - PARTIAL POWER PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.03	1	BLDG. 2 PARTIAL SYSTEMS PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.04	1	BLDG. 2 PARTIAL LIGHTING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.05	1	BLDG. 2 PARTIAL POWER PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.06	1	BLDG. 2 PARTIAL SYSTEMS PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.07	1	BLDG. 1,4 & 5 PARTIAL LIGHTING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.08	1	BLDG. 1,4 & 5 POWER PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.09	1	BLDG. 1,4 & 5 SYSTEMS PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.10	1	BLDG. 3 LIGHTING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.11	1	BLDG. 3 POWER PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E1.12	1	BLDG. 3 SYSTEMS PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E2.01	1	PARTIAL BUILDING 2 - LIGHTING PLAN 2ND FLOOR	10/25/2006	2/7/2006	100	Construction Documents	10/25/06	
E2.02	1	PARTIAL BLDG. 2 - POWER PLAN 2ND FLOOR	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E2.03	1	PARTIAL BLDG. 2 SYSTEMS PLAN 2ND FLOOR	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E2.04	1	PARTIAL BLDG. 2 - 2ND FLOOR LIGHTING PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E2.05	1	PARTIAL BLDG. 2 - 2ND FLOOR POWER PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E2.06	1	PARTIAL BLDG. 2 - 2ND FLOOR SYSTEMS PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E3.01	1	ENLARGED KITCHEN PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref RFls
E3.02	1	ENLARGED ELECTRICAL ROOM AND ELEVATION	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E3.03	1	ENLARGED ELECTRICAL ROOM AND ELEVATION	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E3.04	1	ENLARGED ELECTRICAL ROOM AND ELEVATION	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E3.05	1	ENLARGED ELECTRICAL ROOM AND ELEVATION	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E4.01	1	ELECTRICAL POWER RISER DIAGRAMS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E4.02	0	SYSTEM RISER DIAGRAM	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
E4.03	1	SYSTEM RISER DIAGRAM	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E4.04	0	SYSTEM RISER DIAGRAM	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
E5.01	0	NOTES, LEGEND AND FIXTURE SCHEDULE	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
E5.02	1	MISCELLANEOUS SCHEDULES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E5.03	1	PANELBOARD SCHEDULES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E5.04	1	PANELBOARD SCHEDULES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E5.05	1	PANELBOARD SCHEDULES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E5.06	1	PANELBOARD SCHEDULES	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E5.07	0	PANELBOARD SCHEDULES	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
E6.01	0	MISCELLANEOUS DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
E6.02	0	MISCELLANEOUS DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
E6.03	1	MISCELLANEOUS DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	

C.R. Klewin Southeast, Inc.
 Current Drawing List
 100% Construction Documents - 10/25/06
 PGAL Architects, Inc.

Project # 300600

SCHOOL DISTRICT OF PALM BEACH COUNTY
 PALM BEACH GARDENS ELEMENTARY
 10060 RIVERSIDED DRIVE
 PALM BEACH GARDENS, FL 33410

Number	Rev	Title	Rev Date	Date Received	% Complete	Category	Issue Date/Gen. Notes	Ref. RFIs
E6.04	0	MISCELLANEOUS DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
E6.05	0	MISCELLANEOUS DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
E6.06	1	MISCELLANEOUS DETAILS	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
E6.07	0	ITV TOWER DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
11 - Fire Protection								
FP0.01	0	LEGEND DETAILS AND GENERAL NOTES	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
FP1.01	1	PARTIAL BLDG 2 - FIRST FLOOR PROTECTION PLAN	10/25/2006	2/6/2007	100	Construction Documents	10/25/06	
FP1.02	0	PARTIAL BLDG 2 - FIRE PROTEC. PLAN 2ND FLOOR	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
FP1.03	0	PARTIAL BLDG 2 - FIRE PROTEC. PLAN 1ST & 2ND FLOOR	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
FP1.04	0	BUILDINGS 1 AND 4 - FIRE PROTECTION PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
FP1.05	0	BUILDING 3 - FIRE PROTECTION PLAN	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
FP3.01	0	FIRE PROTECTION PLAN DETAILS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
12 - Food Service								
FS-1	0	FS-1 FOOD SERVICE EQUIPMENT LAYOUT	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
FS-2	0	FOOD SERVICE EQUIPMENT ELECTRICAL LAYOUT	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
FS-3	0	FOOD SERVICE EQUIPMENT PLUMBING LAYOUT	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	
FS-4	0	FOOD SERVICE MECHANICAL AND SPEC CONDITIONS	7/26/2006	2/6/2007	100	Construction Documents	10/25/06	